

#### PO Box 496 • 215 South Cascade Street • Fergus Falls, MN 56538-0496

#### www.bigstoneii.com

February 23, 2007

Mr. Kyrik Rombough
Air Quality Program
South Dakota Department of Environment
and Natural Resources
Joe Foss Building
523 East Capitol
Pierre, SD 57501-3181

FEB 2 6 2007
AIR QUALITY
PROGRAM

Dear Mr. Rombough:

Subject:

Prevention of Significant Deterioration Construction Permit Application

Big Stone II - Update

The purpose of this letter and accompanying enclosures is to update the Big Stone II Prevention of Significant Deterioration Construction Permit Application Updated June 2006 (the Application) to reflect recent site design refinements. This submittal also incorporates PM 2.5 modeling results that are consistent with EPA's National Ambient Air Quality Standards for Particulate Matter which were revised since the submittal of the permit application. (71 FR 61144, October 17, 2006).

#### Facility Design Refinements

#### **Unit Net Electrical Capacity**

The Application refers to the Big Stone II boiler as a nominal 600 MW net pulverized boiler in several locations in the body of the Application and in its appendices. As a result of the more detailed design, the nominal net capacity is expected to be 630 MW. The increased capacity is the result of increased steam cycle efficiency improvements that were incorporated into the design. The design heat input has not increased and it remains at 6,000 mmBtu per hour.

#### **Emissions Units Eliminated**

The design refinements eliminated the coal silos and a result of that decision the following Unit ID's emissions points were eliminated as referenced in the enclosed table that accompanied the Application.

Unit ID	Description
18	Yard Silo Fill System
19	Yard Silo Loadout System
32	Coal Yard Transfer System

Mr. Kyrik Rombough February 23, 2007 Page 2

#### **Emissions Units Added**

The design refinement added two new emission points, a lime storage silo and a soda ash storage silo. The lime and soda ash will be used for water treatment.

Unit ID	Description
34	Pretreatment Soda Ash Bin Vent
35	Pretreatment Lime Bin Vent

#### **Emissions Sources Relocated**

The refinement resulted in the relocation of the following Unit ID emission sources.

- Cooling tower (Unit ID 16)
- Reclaim Hopper (Unit ID 17)
- Limestone Day Bin Vent (Unit ID 24)
- Coal handling diesel fire pump (Unit ID 33)
- Portions of the haul roads

#### Use of Passive Dust Control Design

The passive dust control system design methodology incorporates bulk material flow control and air control. The design helps reduce the amount of induced airflow and the generation of fines in the materials handling transfer system. As an end result materials handling dust can be effectively controlled with significantly reduced discharge airflow as compared to more traditional emission control design. Otter Tail has successfully used this design at a number of materials handling emissions points at its Coyote Station. The passive duct control system design, which reflect the reduced discharge airflow, has been incorporated into the following materials handling particulate emissions control Unit ID's.

Unit ID	Description
17	Emergency Coal Reclaim System
20	Limestone Reclaim System
21	Limestone Receiving System
22	Coal Tripper/Silo Fill System
26	Coal Plant Transfer System
27	Coal Crusher Building
30	Coal Stockout System

#### **Supporting Enclosures**

Enclosed is a revised process flow diagram for the Coal Handling (Drawing No. 060616-00), and a revised process flow diagram for the Limestone Receiving, Storage and Reclaim (Drawing No. 060616-01). The Coal Handling process flow diagram has been updated to reflect the revised design. Note that the size of the active coal pile has been reduced from 75,000 tons to 28,800 tons. The Limestone Receiving, Storage and Reclaim drawing has been revised to correct the designation of Unit ID 28 to Unit ID 29. Please replace the corresponding drawings ins Section 2 of the updated June 2006 Application with the enclosed drawings.

Mr. Kyrik Rombough February 23, 2007 Page 3

Also enclosed are revised Appendix A application forms that incorporate the described changes. Please remove Appendix A from the updated June 2006 Application and replace Appendix A in its entirety. We recognize that Unit ID's are no longer in sequential order, but we would prefer that the Unit ID's remain as designated in order to maintain consistency with the ambient air quality model data inputs.

Finally, enclosed are replacement site arrangement drawings for Appendix B of the updated June 2006 Application.

#### PM2.5 NAAQS Modeling

Burns and McDonnell completed air quality impacts modeling of CO, PM10 and PM2.5 emissions which are described in the enclosed revised permit application Section 6, Section 7 and Appendix C. The modeling protocol has been revised to reflect the redesign as described above and as described in the revised Section 6. Burns & McDonnell will forward the electronic copies of the modeling files to you.

Please note that Big Stone II is proposing to duct the existing rotary car dumper emissions (Unit ID's 7a, 7ab, 7c, and 7d) into a one common stack with a height of 150 feet with no rain cap and a grain loading of 0.01 gr/dscf. Big Stone II is also evaluating the viability of the following control technology options and would plan to implement one of these options in lieu of the increased stack height if the controls are constructible, technically and economically feasible, and the ambient air quality impacts are equal to or less than the increase in stack height.

Option #1-Remove the existing collection equipment and replace it with a fogging system possibly incorporating applicable passive control design that may be applicable to the dumper operation. This would eliminate the emission point. Fogging has been used in similar applications but there are concerns about effectiveness and icing during below freezing conditions during extended periods of time.

Option #2-Modify the dumper area and recalculate 75% of the existing collectors discharge back into the dumper building. The balance of the discharge would flow to a new, common 50-foot stack.

Option #3-Installation of a wet particulate scrubber on the discharge of the collection system/systems. In order for this option to be in consideration the vendor would need to guarantee a discharge better than the bag manufacturer's guarantee of 0.01 gr/dscf.

We plan to complete the evaluation prior to final design and will submit modeling showing that the selected option will have no greater ambient air quality impact than the enclosed modeling results.

Should you have any questions, please contact me at 218-739-8407.

Sincerela

Terry Graumann

Manager, Environmental Services

**Enclosures** 

EXISTING ROTARY DUMPER AND POSITIONER MAGNETIC SEPARATOR CCHA-SEP-21 2CHB -5 6 EXISTING (4) VIBRATING FEEDERS EXHAUST FAN EFAN-27 EXISTING EXISTING 72" TRIPPER CONVEYOR #3 (5) EXISTING 72" EXISTING 72" CONVEYORS
CURRENTLY HANDLE 3,000 TPH.
UPGRADE TO HANDLE 3,600 TPH. CONVEYOR #2 DUST COLLECTOR EXISTING BELT SCALE MAGNETIC -SEPARATOR SEP-22A EXISTING BARN STORAGE 2CHA CARTRIDGE FILTER FLT-21 2CHB MAGNETIC SEPARATOR SEP-22B 72" STOCKOUT BELT CONVEYOR 3,600 TPH CVY-21 EXHAUST FAN EFAN-21 (<del>-</del>) EXHAUST FAN DCO-24 EFAN-25 DUST COLLECTOR DCO-21 SURCE BIN HPR-22 - 2CHC 2CHB STOCKOUT LOWERING WELL LWW-21 DUST COLLECTOR 45 DAYS INACTIVE STORAGE FOR BSP | & II = 681,000 TONS 11.6 ACRES • 45' HIGH ₽ 2CHB CRUSHER ISOLATION SLIDE GATE GAT-28 POSIMETRIC FEEDER FDR-22 EXHAUST FAN 22 EFAN-26 2CHD 2CHC ---------- 2CHB TRIPPER TRAVEL BELT SCALE SCL-22A CRUSHER
BYPASS
DIVERTER GATE EXISTING RECLAIM HOPPER AND FEEDER GAT-27 DUST COLLECTOR DCO-25 PILE CAPACITY 28,800 TONS RECLAIM -GRANULATOR CRUSHER 725 TPH BELT SCALE SCALE SCL-22B (2x0 PRODUCT) CRH-21 CAT-25A GAT-25B
RECLAIM HOPPER
|SLIDE GATES|  $\circ$ 42" TRIPPER CONVEYOR CVY-26A W/TRIPPER TPR-21A CRUSHER DISCHARGE IIVERTER GATE GAT-28 "AS FIRED"
COAL SAMPLING TRAMP
STEM METAL
SAM-21A DETECTOR
TMD-21A RECLAIM O RECLAIM O HOPPER REVERSING BELT FEEDER FDR-23A FDR-23B TRIPPER TRAVEL 42" RECLAIM CONVEYOR 725 TPH CVY-25A 2CHD -- 2CHB 42" RECLAIM CONVEYOR 725 TPH CVY-27A EMISSIONS POINTS (27) (17) COAL RECLAIM SYSTEM COAL CRUSHER BUILDING 42" RECLAIM CONVEYOR 725 TPH CVY-27B 30 COAL STOCKOUT 22 COAL TRIPPER/SILO FILL SYSTEM  $\sigma$ RECLAIM CONVEYOR 725 TPH CVY-258 26 "AS FIRED" \( \)
COAL SAMPLING
SYSTEM
SAW-21B 42" TRIPPER CONVEYOR CVY-269 W/TRIPPER TPR-218 COAL PLANT TRANSFER SYSTEM TRAMP DETECTOR
TMD-218 SILOS NOTES: CDAL CRUSHER BUILDING TRANSFER/COAL SAMPLING BUILDING 1. This drawing is the basis for the coal handling system design and is subject to change as a result of detail design. NOT TO BE USED FOR CONSTRUCTION 2. ALL SYSTEM COMPONENTS ARE AS INDICATED ON THE DRAWING, SUCH AS 2CHB-YYYY-ZZZZ. UNIT #2 ACAD 1=1 BLACK & VEATCH BIG STONE II CO-OWNERS 142662-SS-060616-00 SJRVML MEHMWN SJRVML MEHMWN ORN DES CHK/PDE APP 1 01/16/2007 GENERAL REVISIONS SIGNED DATE VML PROCESS FLOW DIAGRAM -- PERMITTING COAL HANDLING 0 06/16/06 INITIAL ISSUE REG NO. REVISIONS AND RECORD OF ISSUE

L

LIMESTONE RECEIVING DUMPER STRUCTURE -RAIL CAR SIDE SHAKER RCS-1 EXHAUST FAN EFAN-1 LIMESTONE STORAGE STRUCTURE NOTE 3 <del>Ф</del> DUST COLLECTOR DCO-1 LIMESTONE UNLOADING HOPPER -SEE NOTE #4 MAGNETIC SEPARATOR SEP-1 HOPPER OUTLET LIMESTONE UNLOADING
VIBRATING FEEDERS ISOLATION SLIDE GATES 25 FDR-1A FDR-1B FDR-1C (20) 24" LIMESTONE LOADOUT EXHAUST FAN EFAN-2 LIMESTONE COLLECTING CONVEYOR Q LIMESTONE STOCKPILE BELT SCALE CVY-2 SCL-1 CBMC TO WASTE LIMESTONE RECLAIM HOPPERS DUST COLLECTOR HOPPER OUTLET
ISOLATION
SLIDE GATE
GAT-2A -SLIDE GATE GAT-2B DR-28 LIMESTONE CRUSHER BUILDING LIMESTONE RECLAIM VIBRATING FEEDERS MAGNETIC SEPARATOR SEP-2 DUST COLLECTOR SUMP PUMPS DRAIN -24" LIMESTONE RECLAIM CONVEYOR CVY-3 P-1B LIMESTONE PREPARATION BUILDING LIMESTONE CRUSHER SURGE BIN DUST COLLECTOR LIMESTONE CRUSHER CRH-1 24" LIMESTONE FEED BIN FILL CONVEYOR — TO WASTE DMERTER GATE M CVY-5 SUMP PUMPS CBMB NOTES EMISSIONS POINTS This drawing is the basis for the limestone receiving, storage and reclaim system and is subject to revision as a result of detailed design. P-2A P-28 CBMC (20) LIMESTONE RECLAIM SYSTEM 2. ALL SYSTEM COMPONENTS ARE SERIES CHMA-YYYY-ZZZZ, UNLESS OTHERWISE SPECIFIED. 3. STRUCTURE TO BE PROVIDED OVER LIMESTONE UNLOADING HOPPER FOR DUST CONTROL AND PROTECTION FROM WEATHER.

4. STRUCTURE TO BE PROVIDED OVER LIMESTONE STORAGE AND RECLAIM AREA FOR PROTECTION FROM WEATHER. (21) LIMESTONE RECEIVING SYSTEM (24) LIMESTONE DAY BINS VENT LIMESTONE STOCKOUT CONVEYOR (FUGITIVE) NOT TO BE USED FOR CONSTRUCTION **29**) BLACK & VEATCH BIG STONE II CO-OWNERS 142662-SS-060616-01 1 1 01/16/2007 GENERAL REVISIONS SURVAL MEHAWA SURVAL MEHAWA DRN DESCHRIPDE APP PROCESS FLOW DIAGRAM -- PERMITTING LIMESTONE RECEIVING, STORAGE AND RECLAIM 0 06/16/2008 INITIAL ISSUE SIGNED DATE REVISIONS AND RECORD OF ISSUE

1

#### 6.0 AIR DISPERSION MODELING

Since this project is subject to PSD review, an air dispersion modeling analysis is required for each pollutant subject to 40 CFR Part 52.21. According to the emission estimates for this project, CO and  $PM_{10}$  are subject to PSD review, and an air quality analysis was performed for each. Since VOCs are photoreactive pollutants and are generally regional in nature in terms of their contribution to ozone formation, no reactive-pollutant modeling of VOCs was conducted. In addition, Big Stone II requests that a pre-construction ambient ozone monitoring study not be required since potential VOC emissions are expected to be less than 100 tpy.

The results of the modeling indicate that the impacts of CO from Big Stone II will not result in a significant impact at any location. According to the draft "New Source Review Workshop Manual," no further modeling is required for a PSD applicant if the modeled impacts are below the significance levels. However, the modeling analyses show that Big Stone II's emissions exceed the PSD *de minimis* modeling significance thresholds for PM<sub>10</sub>. A refined modeling analysis will be conducted for the annual PM<sub>10</sub> averaging period and the 24-hour PM<sub>10</sub> averaging period to demonstrate compliance with the National Ambient Air Quality Standards (NAAQS) and PSD Class II Increments. Additionally, a modeling analysis will be conducted for the annual PM<sub>2.5</sub> averaging period and the 24-hour PM<sub>2.5</sub> averaging period to demonstrate compliance with the NAAQS.

#### 6.1 Air Dispersion Model

Air dispersion modeling was performed using the most current version of the AMS/EPA Regulatory Model (AERMOD) for the air quality analysis (Version 07026). The AERMOD is an EPA-approved, steady state Gaussian plume model capable of modeling multiple sources in simple and complex terrain. AERMOD is the model currently approved for industrial sources and PSD permits.

The following default model options were used:

- Gradual Plume Rise
- Stack-tip Downwash
- Buoyancy-induced Dispersion
- Calms and Missing Data Processing Routine
- Calculate Wind Profiles
- Calculate Vertical Potential Temperature Gradient
- Rural Dispersion

Details of the modeling algorithms contained in the AERMOD may be found in the User's Guide for AERMOD. The regulatory default option will be selected for this analysis since this project meets the USEPA guideline requirements.

#### 6.2 Model Stack Parameters

#### 6.2.1 Big Stone II

Modeling runs were conducted confirm that operation of Big Stone II will not result in impacts greater than the NAAQS or PSD increments. The stack parameters used in the analysis are given in Table 6-1. Emission rates for each of the pollutants at each operating load are given in Table 6-2.

Table 6-1: Big Stone II – Boiler Stack Parameters

Stack	Stack Stack		city (ft/s)	Stack Temp. (°F)	
Height	Diameter	Boiler 2 Only	Both Boilers	Boiler 2 Only	Both Boilers
498 ft	34 ft	33.89	63.57	136	137

**Table 6-2: Boiler Potential Emission Rates** 

Pollutant	Capacity Emissions (lb/hr)			
) Ollatalit	Boiler 2 Only	Both Boilers		
CO	900.00	1,358.20		
$PM_{10}$	180.00	1,688.00		

All emissions were modeled to correspond to their BACT emission levels.

#### 6.2.2 Haul Roads

All haul roads will be paved as part of the Big Stone II project. Paved roads will be swept and/or wetted with water or another dust suppression agent as needed to control fugitive dust. Paved road emission factors were used to calculate the emissions from all haul road segments with a 50% control efficiency factor to account for the fugitive dust controls. Figure 6-1 shows the road layouts.

Annual usage of haul roads is calculated as the maximum expected annual material tonnage plus 20% margin as noted in Appendix C.




Figure 6-1: Facility Haul Roads

#### 6.3 Good Engineering Practice

Sources included in a modeling analysis at a PSD major facility are subject to Good Engineering Practice (GEP) stack height requirements outlined in 40 CFR Part 51, Sections 51.100 and 51.118. As defined by the regulations, GEP height is calculated as the greater of 65 meters (measured from the ground level elevation at the base of the stack) or the height resulting from the following formula:

$$GEP = H + 1.5L$$

Where,

H = the building height; and

L = the lesser of the building height or the greatest crosswind distance of the building - also known as maximum projected width.

To meet stack height requirements, the proposed point sources will be evaluated in terms of their proximity to nearby structures. The purpose of this evaluation is to determine if the discharge from each stack will become caught in the turbulent wake of a building or other structure, resulting in downwash of the plume. Downwash of the plume can result in elevated ground-level concentrations. EPA provides guidance for determining whether building downwash will occur in *Guideline for Determination of Good* 

Engineering Practice Stack Height (EPA, 1985). The downwash analysis will be performed consistent with the methods prescribed in this guidance document. The generation facility and associated point sources will be evaluated in terms of their proximity to nearby structures.

Calculations for determining the direction-specific downwash parameters will be performed using the most current version of the EPA's Building Profile Input Program – Plume Rise Model Enhancements, otherwise referred to as the BPIP-PRIME downwash algorithm.

Every stack, including dust collectors and diesels, has been evaluated for GEP stack height compliance. This data is found in Appendix G on the CD-ROM in the file entitled 070216run6.SUM.

#### 6.4 Receptor Grid

The overall purpose of the modeling analysis is to ensure that operation of the proposed facility will not result in, or contribute to concentrations above the National Ambient Air Quality Standards (NAAQS) or PSD Class II increments. The modeling runs were conducted using the AERMOD model in simple terrain within a 7 by 4.5 kilometer Cartesian grid to determine the impacts for each pollutant. The grid incorporated the 100-meter spacing between receptors. Additionally, receptors were placed along the property boundary at a spacing of 50 meters. After reviewing the topography of the area, it was determined that terrain elevations should be incorporated into the model. Therefore, the appropriate United States Geological Survey (USGS) 7.5 minute topographical maps (from electronic DEM data) were used to obtain the necessary receptor elevations.

#### 6.5 Meteorological Data

Surface air meteorological data from Huron, SD (14936) with Aberdeen, SD (14929) upper air data from 2001-2005 was used in the analysis. The profile base elevation is 390.1 meters. The dominant wind direction is shown in Figure 6-2. The raw data had missing values for a five hour period on February 9, 2002 (hours 13 through 17). These values were filled in using data from the same time period from Mitchell, SD.




Figure 6-2: Big Stone Power Plant Windrose

#### 6.6 Rural Dispersion Coefficients

Based on the Auer scheme, the existing land use for a three-kilometer area surrounding the proposed site is more than 50 percent rural. The population density is also less than 750 people/km<sup>2</sup> for the same area. Rural coefficients are appropriate for the Big Stone II area. Therefore, rural dispersion coefficients were used in the AERMOD Model.

#### 6.7 Significant Impact Area Determination

The AERMOD model was run for the proposed facility using the worst-case capacity scenario for the coal-fired boiler. If any modeled pollutant results in an impact below the significance levels for each averaging period, no further modeling for that pollutant to determine compliance with the NAAQS or PSD Class II increments is needed. However, if the model predicts impacts at or above the modeling significance level for any pollutant, a cumulative analysis including all point sources within the radius of impact (ROI) will be required for that pollutant. Based on the initial modeling results, Big Stone requested from DENR an emission inventory of PSD increment-consuming sources and NAAQS sources that are located within the ROI and should be included in the modeling analyses.

#### 6.8 NAAQS and Class II Increment Analysis

For the NAAQS and PSD increment analysis, all major stationary sources that emit pollutants subject to this analysis and located within 50 kilometers of the ROI were addressed. A source within 50 kilometers of the impact area may be eliminated from the analysis if it is determined to have a negligible contribution to air quality impacts at the generating station. Big Stone consulted with the DENR to determine

acceptable methods of eliminating sources from the analysis. Background air quality values for Grant County are available from the DENR to add to model-predicted concentrations for comparison to the NAAQS and are shown in Table 6-3. If the refined analysis does not result in any concentrations above the NAAQS or PSD increments, no further modeling will be conducted.

Table 6-3: Background Levels (µg/m³)

PM <sub>10</sub> 24 Hr		
32	17	8

#### 6.9 Ambient Monitoring

The modeling analysis for emission sources at the proposed Big Stone facility also addressed the preconstruction monitoring provision of the PSD regulations. The regulations specify significant monitoring levels for each PSD pollutant that triggers the requirement to perform one year of pre-construction ambient air monitoring. For any impacts predicted to be below the monitoring significance levels, Big Stone will request an exemption from pre-construction ambient air monitoring. If any predicted concentrations reaching or exceeding the monitoring *de minimis* levels are observed, Big Stone will consult with the DENR to determine if pre-construction ambient air monitoring will be required. If so, Big Stone will request local ambient monitoring data to fulfill the pre-construction monitoring provisions of the PSD regulations or develop an acceptable monitoring plan. Table 6-4 shows the NAAQS, modeling/monitoring significance levels, and PSD increments.<sup>1</sup>

Table 6-4: NAAQS, Significance Levels and Class I and II increments (µg/m³)

Pollutant	Averaging Period	NAAQS	Modeling Significance Level	Monitoring Significance Level	PSD Class II Increments
СО	8-hour	10,000	500	575	NA
	1-hour	40,000	2,000	NA	NA
DM (	Annual	50	1	NA	17
PM <sub>10</sub>	24-hour	NA	5	10	30
DM	Annual	15	NA	NA	NA
PM <sub>2.5</sub>	24-hour	35	NA NA	NA	NA

<sup>&</sup>lt;sup>1</sup> The pollutants that are allowed one NAAQS exceedance per year and one PSD Increment exceedance per year are: 1-hour and 8-hour CO and 24-hour PM/PM<sub>10</sub>.

#### 6.10 Screening Model Results

After examining the modeling results at all load levels, it was determined that exceedances of the annual modeling significance level occurred, and that refined modeling would be required. All predicted impacts were lower than the ambient air monitoring *de minimis* level and no pre-construction monitoring was required. The maximum modeled concentrations are given in Table 6-5. The model input and output files are provided on CD-ROM in Appendix G.

Table 6-5: Screening Level Maximum Modeled Concentrations

Pollutant	Averaging	UTM Coordinates (meters)		Year	Predicted Concentration	Modeling/ Monitoring Significance	
	Period	Easting	Northing		(μg/m³)	Level (μg/m³)	
СО	1-hour	695200.00	5018800.00	2002	495.82	2,000	
	8-hour	695200.00	5018800.00	2005	301.34	500/575	

#### 6.11 PM<sub>10</sub> NAAQS Modeling Results

After examining the modeling results, it was determined that Big Stone II will not cause the NAAQS to be exceeded at any point where the facility will have a significant impact. Table 6-6 lists the results from the NAAQS analysis.

Table 6-6: PM<sub>10</sub> NAAQS Modeling Results (μg/m³)

Averaging Period	NAAQS	Maximum Modeled Impact				Background Concentration	Total Concentration
		Easting	Northing	Year	Concentration		
24-hour	150	695200.00	5018900.00	2005	64.97	32.00	96.97

#### 6.12 PM<sub>10</sub> Class II Increment Modeling Results

After examining the modeling results, it was determined that Big Stone II will not cause the PSD Increment to be exceeded at any point where the facility will have a significant impact. Table 6-7 lists the results from the NAAQS analysis.

Table 6-7: PM<sub>10</sub> Increment Modeling Results (μg/m³)

Averaging Period	PSD Increment	ı	Maximum Mode All NAAQS	act:	
		Easting	Northing	Year	Concentration
24-hour	30	695063.62	5019008.00	2005	29.76
Annual	17	695074.81	5019022.50	2001	5.03

#### 6.13 Concentration Contour Plot

Per DENR's request, the concentration contour plots for  $PM_{10}$  annual average at 1  $\mu g/m^3$  is shown in Figure 6-3.

#### 6.14 PM<sub>2.5</sub> NAAQS Modeling Results

EPA adopted a NAAQS for PM<sub>2.5</sub> in 1998 but has yet to adopt an implementing rule. In guidance, EPA has indicated that it is appropriate to use PM<sub>10</sub> as a surrogate parameter for determining compliance with the PM<sub>2.5</sub> standard. (Memorandum from John S, Seitz, Director Office of Air Quality Planning and Standards to Regional Air Directors, "Interim Implementation of New Source Review for PM<sub>2.5</sub>" (October 23, 1997); reconfirmed in Memorandum from Stephen D. Page to Addressees, "Implementation of New Source Review Requirements in PM<sub>2.5</sub> Non-attainment Areas" (April 5, 2005)). To address questions raised in public comments, the application included modeling for PM<sub>2.5</sub> using the following conservative assumptions:

- All PM<sub>10</sub> emissions from stacks were assumed to be equal to PM<sub>2.5</sub>
- Emissions from drop points were recalculated using the k factor for PM<sub>2.5</sub> from AP-42 section 13.2.4. ( $k_{2.5} = 0.053$ )
- Emissions from paved haul roads were recalculated using the k and c factors for PM<sub>2.5</sub> from AP-42 section 13.2.1. ( $k_{2.5} = 0.0024$ )
- Emissions from unpaved haul roads (pile maintenance) were recalculated using the k factor for PM<sub>2.5</sub> from AP-42 section 13.2.2. (k<sub>2.5</sub> = 0.15)
- Emissions from storage pile wind erosion were recalculated using the k factor for PM<sub>2.5</sub> from AP-42 section 13.2.5. ( $k_{2.5} = 0.075$ )

After examining the modeling results, it was determined that Big Stone II will not cause the PM<sub>2.5</sub> NAAQS to be exceeded at any point where the facility will have a significant impact. Table 6-8 provides a summary of the results from the PM<sub>2.5</sub> NAAQS analysis. The resulting total concentrations modeled plus background are below the applicable NAAQS for PM<sub>2.5</sub>.

Table 6-8: PM<sub>2.5</sub> NAAQS Modeling Results (μg/m³)

Averaging Period	NAAQS	ı	Maximum Modeled Impact: All NAAQS Sources				Total Concentration
		Easting	Northing	Year	Concentration	Concentration	Concentiation
24-hour	35	695034.62	5018977.00	2002	17.18	17.00	34.18
Annual	15	695074.81	5019022.50	2004	5.31	8.00	13.31

#### 6.15 Conclusion

The dispersion modeling predicts that there will be no exceedances of the Increment and NAAQS thresholds. The operation of the Big Stone II Project will not cause or contribute to a significant degradation of ambient air quality. After examining the results of the model, it has been determined that the PSD modeling requirements for CO and PM<sub>10</sub> have been met and no further modeling is required.




Figure 6-3: PM<sub>10</sub> Increment Annual Average (1 µg/m<sup>3</sup>)

#### **BIG STONE !!**

#### 7.0 ADDITIONAL IMPACTS

The additional impacts analysis requirement under PSD assesses the ambient air quality impact analysis, soils and vegetation impacts, visibility impairment, and growth analysis for the project.

#### 7.1 Construction Impacts

Construction of Big Stone II has the potential for short-term adverse effects on air quality in the immediate area around the site. Diesel fumes from construction vehicles and dust from site preparation and construction vehicle operation can affect local air quality during certain meteorological conditions. However, these instances are limited in time and area of effect.

The Grant County area is in attainment or is unclassified for all criteria pollutants. Operation of construction vehicles is not expected to significantly affect ambient air quality. During dry periods, fugitive dust will be minimized through the application of water to on-site roads used by construction equipment.

#### 7.2 Vegetation Impacts

Vegetation in the region of eastern South Dakota and western Minnesota was historically dominated by tallgrass prairie in an area referred to as the Prairie Parkland Region<sup>2</sup>. Glaciation left this area with a mosaic of rolling glacial till uplands and pothole depressions. In areas that haven't been developed or converted to cropland, tallgrass prairie dominates the drier, exposed upland areas and commonly consists of big bluestem (*Andropogon gerardii*), Indian grass (*Sorghastrum nutans*), little bluestem (*Schizachyrium scoparium*), switchgrass (*Panicum virgatum*), prairie dropseed (*Sporobolous heterolepis*), and porcupine grass (*Hesperostipa spartea*). Areas that are more protected from dry, hot conditions by moisture or east- to north-facing slopes more commonly consist of savannas, woodlands or forests dominated by oaks (*Quercus* spp.), eastern cottonwood (*Populus deltoides*), ash (*Fraxinus* spp.), and willows (*Salix* spp.).

The following sections briefly describe the potential effects of NO<sub>2</sub>, SO<sub>2</sub>, CO, and PM<sub>10</sub> produced by Big Stone II on the nearby vegetation. The potential effects of the air emissions to vegetation within the immediate vicinity of the Big Stone Power Plant were compared to scientific research examining the

-

<sup>&</sup>lt;sup>2</sup> Faber-Langendoen 2001

effects of pollution on vegetation. Damage to vegetation often results from acute exposure to pollution, but may also occur after prolonged or chronic exposures. Acute exposures are typically manifested by internal physical damage to leaf tissues, while chronic exposures are more associated with the inhibition of physiological processes such as photosynthesis, carbon allocation, and stomatal functioning.

#### 7.2.1 Sulfur Dioxide

Short- and long-term exposure to sulfur dioxide has been shown to have detrimental effects on many plant species<sup>3</sup>. Numerous studies have been conducted studying the effects of SO<sub>2</sub> on vegetation including crop plants<sup>4</sup>, trees and shrubs<sup>5</sup>, and herbaceous plants<sup>6</sup>. Symptoms of SO<sub>2</sub> injury in leaves manifest as interveinal necrotic blotches in angiosperms and red brown banding in gymnosperms<sup>7</sup>. A number of the plants studied include those found in the Prairie Parkland Region or are raised for agriculture in the area. Plants include red cedar (*Juniperus virginiana*), oaks, sumacs (*Rhus* spp.), ash, raspberries (*Rubus* spp.), American elm (*Ulmus americana*), red maple (*Acer rubrum*), black willow (*Salix nigra*), bracken fern (*Pteridium aquilinum*), soybean (*Glycine max*), and corn (*Zea mays*). Injury threshold concentrations varied by species and dose (131-5,240 μg/m<sup>3</sup> for 8 hours, 393-3,930 μg/m<sup>3</sup> for 2 hours, and 1,310 μg/m<sup>3</sup> for 4 hours), and were significantly higher than the SO<sub>2</sub> emissions expected to occur near the Big Stone Power Plant. Even lichens and bryophytes, which are pollution bio-indicators due to their well-documented sensitivity to air pollution, would not be affected by long term exposure to SO<sub>2</sub> emissions from Big Stone II. They do not experience injury, decreased abundance, or lowered CO<sub>2</sub> uptake until SO<sub>2</sub> concentrations reach 5 to 40 μg/m<sup>3</sup> SO<sub>2</sub><sup>8</sup>, 13 to 26 μg/m<sup>3</sup> SO<sub>2</sub><sup>9</sup> and 400 μg/m<sup>3</sup> SO<sub>2</sub><sup>10</sup> annually.

#### 7.2.2 Nitrogen Oxides

During fuel combustion, atmospheric nitrogen is oxidized to nitrogen oxide and small amounts of NO<sub>2</sub><sup>11</sup>. The NO is photochemically oxidized to NO<sub>2</sub>, which is then subsequently consumed during the production of ozone and peroxyacetyl nitrates (PANs). As with SO<sub>2</sub> emission research, NO<sub>2</sub> has been shown to deleteriously impact vegetation<sup>12</sup>. Typical leaf injury responses include interveinal necrotic blotches similar to SO<sub>2</sub> injury for angiosperms and red-brown distal necrosis in gymnosperms<sup>13</sup>. Injury threshold concentrations vary by species and dose, but are much higher than that of SO<sub>2</sub> as described above. In

<sup>&</sup>lt;sup>3</sup> See reviews by Heath 1980; Kozlowski and Constantinidou 1986; Darrall 1989

<sup>&</sup>lt;sup>4</sup> Guderian and Stratman (1968) in Kozlowski and Constantinidou 1986; Huang et al. 1976; Reinert et al. 1975; Tingey et al. 1971; Darrall 1989

<sup>&</sup>lt;sup>5</sup> Linzon 1986; Kozlowski and Constantinidou 1986; Darrall 1989

<sup>&</sup>lt;sup>6</sup> Winner and Mooney 1980; Westman et al. 1985; Darrall 1989

<sup>&</sup>lt;sup>7</sup> Kozlowski and Constantinidou 1986

<sup>8</sup> Will-Wolf 1980; Holopainen 1984; McCune 1988; and Treshow and Anderson 1989

<sup>&</sup>lt;sup>9</sup> LeBlanc and Rao 1975; Wetmore 1988

<sup>10</sup> Hart et al. 1988

<sup>11</sup> Chang 1981

<sup>&</sup>lt;sup>12</sup> Taylor et al. 1975; Heath 1980; Kozlowski and Constantinidou 1986; and Darrall 1989

<sup>&</sup>lt;sup>13</sup> Kozlowski and Constantinidou 1986

general, short term high, concentrations of NO<sub>2</sub> are required for deleterious impacts on plants<sup>14</sup>. The injury threshold for two crop plants grown in the region - tomato (Lycopersicon esculentum) and annual sunflower (Helianthus annuus) – is 4 hours at a concentration of 7,380 µg/m<sup>3</sup>. A common, weedy plant found throughout the Prairie Parkland Region, lamb's quarters (Chenopodium album), was not injured for two hours at concentrations 1.9 ug/m<sup>3</sup> NO<sub>2</sub>. Furthermore, short term fumigations of approximately 1 hour, 20 hours, and 48 hours at NO<sub>2</sub> concentrations of 940 to 38,000 μg/m<sup>3</sup>, 470 μg/m<sup>3</sup>, and 3,000 to 5,000 µg/m<sup>3</sup>, respectively, have been shown to deter photosynthesis in a number of herbaceous [tomato, oats (Avena sativa), alfalfa (Medicago sativa)] and woody plants<sup>15</sup>. Moreover, Taylor and McLean (1970), in their review of NO<sub>2</sub> effects on vegetation noted that long term exposures of phytotoxic doses of NO<sub>2</sub> ranged from 280 to 560 μg/m<sup>3</sup>. All the above concentrations are significantly higher than the NO<sub>2</sub> emissions expected to occur near the Big Stone Power Plant.

#### 7.2.3 Synergistic Effects of Pollutants

Air pollutants are known to act in concert to cause injury to or decrease the functioning of plants<sup>16</sup>. Synergistic refers to the combined effects of pollutants when they are greater than is expected from the additive effect of the compounds. The inhibitory effects of SO<sub>2</sub> and NO<sub>2</sub><sup>17</sup>, NO<sub>2</sub> and NO<sub>3</sub><sup>19</sup> and O<sub>3</sub> and SO<sub>2</sub><sup>20</sup> have been reported in various short-term studies for crop plants (e.g., soybean, broad bean (Vicia faba), annual sunflower, and tomato) and various trees that grow in the Prairie Parkland Region [e.g., eastern cottonwood, sugar maple (Acer saccharum), ash, and oak]. Concentrations of pollutants (80 to 981 µg/m<sup>3</sup>) in these studies are substantially higher than concentrations predicted to occur near the Big Stone Power Plant. Consequently, no synergistic effects of the air pollutants are expected to inhibit vegetation at or near the Big Stone Power Plant.

#### 7.2.4 Particulate Matter

Particulates may contain trace elements and heavy metals such as arsenic, boron, beryllium, copper, fluoride, nickel, lead, mercury, manganese, and cobalt<sup>21</sup>. These compounds have been shown to be detrimental to vegetation typically within the immediate vicinity of the source<sup>22</sup>. The most obvious effect of particle deposition on vegetation is a physical smothering of the leaf surface. This will reduce light

<sup>12</sup> Prinz and Brandt 1985

Hill and Bennett 1970; Capron and Mansfield 1976; and Smith 1981
 See reviews of Reinert et al. 1975; Omrod 1982

<sup>&</sup>lt;sup>17</sup> White et al. 1974; Wright et al. 1986 <sup>18</sup> Capron and Mansfield 1976

<sup>19</sup> Furakawa et al. 1984; Okana et al. 1985

<sup>&</sup>lt;sup>20</sup> Costonis 1970, Carlson 1979; Jensen 1981; Omrod et al. 1981

<sup>&</sup>lt;sup>21</sup> Wangen and Turner 1980

<sup>22</sup> Woolhouse 1990

transmission to the plant, in turn causing a decrease in photosynthesis<sup>23</sup>. However, only small amounts of particulate matter are emitted from power plants. Particulate matter concentrations due to operation of Big Stone II are expected to increase by 2.43  $\mu$ g/m³. These levels are considered negligible, so it is highly unlikely that particulate matter emissions will impact vegetation adjacent to the Big Stone Power Plant.

#### 7.2.5 Carbon Monoxide

Carbon monoxide is not known to injure plants nor has it been shown to be taken up by plants.

Consequently, no adverse impacts to vegetation at or near the Big Stone Power Plant are expected from CO stack emissions.

#### 7.3 Soil Impacts

Eight soil mapping units have been identified at or in the immediate vicinity of the project site<sup>24</sup>. They include:

- Heimdal-Sisseton loams, 2 to 6 percent slopes (HbB)
- Heimdal-Sisseton loams, 6 to 9 percent slopes (HbC)
- Heimdal-Svea loams, 0 to 2 percent slopes (HcA)
- Heimdal-Svea loams, 2 to 6 percent slopes (HcB)
- Vallers-Tonka complex (Vc)
- Parnell silty clay loam
- Tonka silt loam (Ta)
- Vallers loam

Sulfates and nitrates caused by SO<sub>2</sub> and NO<sub>2</sub> deposition on soil can be beneficial and detrimental to soils depending on their composition. However, given the low emission impacts, Big Stone II should not significantly affect the soils on site or in the immediate vicinity.

#### 7.4 Impacts on Threatened and Endangered Species

The following discussion on threatened and endangered species is based on Barr Engineering's assessment as contained in the South Dakota Energy Conversion Facility Siting Permit Application for Big Stone II.

<sup>&</sup>lt;sup>23</sup> Meteorological Service of Canada 2002

The U.S. Fish and Wildlife Service has identified three federally listed species that may occur in the project area (USFWS/Gober 2004, September 16, 2004 letter to Jeffrey Lee/Barr Engineering). They are the Bald eagle (*Haliaeetus leucocephalus*), the Topeka shiner (*Notropis topeka*), and the western prairie fringed orchid (*Platanthera praeclara*).

The bald eagle, a federally threatened species, is known to occur in Grant County and throughout South Dakota. New nests appear in Grant County and in South Dakota in general each year, and the birds nest from January through August. The USFWS restricts construction within one-quarter (0.25) mile of an active bald eagle nest. A bald eagle nest was identified and mapped approximately 1700' (0.3 mile) north of the existing east water storage and cooling pond. The nest is nearly 1.5 miles northwest of the proposed Big Stone II plant site, and over 1.5 miles from the proposed cooling tower. It is nearly 3 miles northwest of the proposed new water storage pond.

The Topeka shiner, a federally endangered species, is listed as a "possible" occurrence in Grant County. The species is not listed as South Dakota state threatened or endangered. The South Dakota Department of Game, Fish and Parks has no current or historic locations of the Topeka shiner in Grant County, and all known occurrences of the Topeka shiner in South Dakota are in streams south southeast of Grant County (S. Dakota Dept. of Game, Fish and Parks 2003. Topeka Shiner Management Plan for South Dakota.).

Construction of the Big Stone II plant is not likely to result in any direct, indirect or cumulative impacts on the Topeka shiner. This is because the only potential habitat for the fish, the Whetstone River, is outside of the construction limits of the project, and will receive no discharge from the plant. In the event that, prior to or during construction, the Topeka shiner is found in the Whetstone River, the South Dakota Department of Transportation Special Provisions for Construction Practices in Streams Inhabited by the Topeka Shiner (SDDOT 2003) can be implemented.

The western prairie fringed orchid, a federally threatened species, is also listed as a "possible" occurrence in Grant County. There are currently no known populations of this plant species in South Dakota. However, the species has historically been distributed throughout the tall grass prairie west of the Mississippi River in the Central United States and southern Canada, and one of the three largest remaining populations is approximately 122 miles north of the Big Stone II site. Moreover, the species' preferred habitat of mesic prairie swales exists in several small areas within the Big Stone II project area.

<sup>24</sup> Miller 1979

A number of the known plant associates of the western prairie fringed orchid are also present, including big bluestem (*Andropogon gerardii*), little bluestem (*Schizachyrium scoparium*), and several sedge (*Carex* spp.) species.

Field surveys conducted in September 2004 did not locate any populations of western prairie fringed orchid. As a result, there are currently no anticipated direct impacts on this species. Indirect impacts include loss of potential habitat, alteration of surface drainage patterns and a potential increase in non-native invasive species.

Operation of Big Stone II should not cause any adverse impacts to protected species or potential habitats since facility air emissions meet all ambient air quality standards and PSD increments. Consultation under Section 7 of the Endangered Species Act regarding the Big Stone II project is being conducted in conjunction with an Environmental Impact Statement under the National Environmental Policy Act being prepared by the Western Area Power Administration. DENR is required to coordinate its PSD review for Big Stone II "to the maximum extent feasible and reasonable" with the EIS review. 40 CFR 52.21(s).

#### 7.5 Growth Impacts

Big Stone II is expected to increase employment in the area. The building phase will last approximately four years. Construction employment of approximately 700 workers is expected over the course of the construction period. Projected employment, reflecting full time jobs directly tied to the operation of Big Stone II, is estimated at 35 additional people at the generating station site. This will result in moderate amounts of secondary employment created by the economic activity of the plant. In the immediate vicinity of the plant and as a result of Big Stone II, residential and commercial growth will result in secondary air emissions (i.e. increased vehicular use) but are not expected to significantly impact air quality.

#### 7.6 Class II Area Visual Impact Analysis

A visibility analysis was performed on the Pipestone National Monument in southwestern Minnesota. The visibility analysis was performed in accordance with the guidelines set forth in EPA-450/4-88-015, Workbook for Plume Visual Impact Screening and Analysis. Within the document, the model VISCREEN is recommended for plume visibility analysis. Several refinement levels of VISCREEN are described. The first level VISCREEN analysis uses worst-case meteorological conditions (F-class stability, 1 m/s wind speed). This level of screening results in the most conservative (worst-case) visibility results. If the plume visibility against the sky and terrain is below a level perceivable to the

human eye, the visibility modeling is complete. Otherwise, a second level VISCREEN analysis, that uses actual meteorological data and refined particle characteristics, can be performed. The second level model will result in a more realistic visibility analysis. If this plume visibility still does not meet sky and terrain contrast levels, a third level model may be required that adds more statistical analysis.

The first level VISCREEN model was performed for Big Stone II. Emissions from Big Stone II only were considered. The inputs into the model included particulate matter, NO<sub>X</sub>, primary NO<sub>2</sub>, soot, and primary SO<sub>4</sub>. The maximum annual particulate emissions from Big Stone II are 788 tons/yr<sup>25</sup>. The corresponding NO<sub>X</sub> emission rate is 1,840 tons/yr.

According to the workbook, primary NO<sub>2</sub>, soot, and primary SO<sub>4</sub> can be assumed to be zero except for very specific sources. Since the power plant is not one of the specified sources, the emissions for the last three species (primary NO<sub>2</sub>, soot, and primary SO<sub>4</sub>) are assumed to be zero. The next set of inputs into the level one VISCREEN model considers the distance between the source, observer and area, and the background visual range. The distance between the source and observer is 145 kilometers.

Background visibility was determined from the VISCREEN manual to be 40 kilometers. The last inputs into the model are particle sizes, background ozone, plume-source-observer angle, stability, and wind speed. All of these inputs are automatically set if the default option is chosen. For the level one analysis, the workbook tells the analyst to choose the default option, which sets the following particle sizes:

- background fine = 0.3 μm diameter, 1.5 g/cm<sup>3</sup> density
- background course = 6 μm diameter, 2.5 g/cm³ density
- plume particulate =  $2 \mu m \text{ diameter}$ ,  $2.5 \text{ g/cm}^3 \text{ density}$
- plume soot =  $0.1 \mu m$  diameter,  $2 \text{ g/cm}^3$  density
- plume primary sulfate =  $0.5 \mu m$  diameter,  $1.5 \text{ g/cm}^3$

The background ozone is 0.04 parts per million (ppm), the plume-source-observer angle is 11.25 degrees, the worst case atmospheric stability is an F stability class, and the worst case wind speed is 1 m/s.

The VISCREEN model output compares the calculated Delta E and contrast from the plume to present default comparison values. Delta E is the color difference parameter used to characterize the perceptibility of the plume on a color difference between the plume and a viewing background such as the

<sup>&</sup>lt;sup>25</sup> Emissions are only from the boiler. Not including emissions from materials handling or fugitive emissions.

sky, a cloud, or a terrain feature. Color differences are due to differences in three dimensions: brightness (L\*), color hue (a\*), and saturation (b\*). Delta E is calculated for several lines of sight. A green contrast analysis is also performed for various lines of sight using a green wavelength and contrasting the plume with the terrain and sky backgrounds. The critical E value is 2.0 and the green contrast value is 0.05.

The results of the Level 1 VISCREEN model are shown in Appendix H. The visual results pass the Class I screening criteria at the Pipestone National Monument located 145 km away. With respect to visibility conditions around the plant, there are no known Class II screening visibility criteria that have been recommended at this time. Big Stone II will be constructed in a Class II area. Operation of the proposed emission sources will demonstrate compliance with state regulations restricting stack gas opacity to 20 percent. Big Stone believes that if emissions comply with these levels, no adverse visibility impacts will occur in the immediate vicinity around the plant.

#### 7.7 Conclusion

Based upon the results presented in this section of the report, it is concluded that the construction of Big Stone II will not have a significant adverse impact on the surrounding area.



### Air Quality Permit Application Form Title V (Part 70) Operating Permit

# General Information Form And Certification of Applicant Form

#### **SEND ALL MATERIALS TO:**

SD Department of Environment and Natural Resources Air Quality Program 523 East Capitol Pierre, South Dakota 57501-3181

(Please complete shaded areas - if you have questions call (605) 773-3151)

#### A. GENERAL INFORMATION

If permit is being renewed or	r amended, give existing permit number:	28.0801-29				
1. Facility name:	Big Stone Power Plant	Sinch in perincipal proprieta proprieta de la companya de la companya de la companya de la companya de la comp Companya de la companya de la compa				
2. Mailing address:						
Street and/or box number	215 South Cascade Street					
City, state, zip code	Fergus Falls, MN 56537	iki Aligania in nich naminim mamamunga di sentrum kanan dengera pelebulaha Majin anaman manada naminim sentrum kanan dianggan sentrum kanan dianggan kanan dianggan kanan dianggan kanan d				
3. Facility location (if plant	is portable, enter location at time of submit	tal):				
Street and city	Big Stone City					
Legal description and county	Grant County					
	(Quarter, Section,	Township, Range)				
4. Permit contact:						
Name/title	Terry Graumann, Manager Environmenta	l Services				
Telephone number	218-739-8407					
5. Facility contact, if different	nt than permit contact (Person to contact for	or arranging inspections):				
Name/title	and the Bornald Studie halfe halfeen peal think miller hiller an said in a dhai	ik ing palan i amping gerija pada Stalindia ar utas menindia retubektur. Mahala apalamenter di uterah dalam 1881 di Japin di Uterah kanga ta				
Telephone number						
6. Responsible official:						
Name/title	Terry Graumann, Manager Environmenta	l Services				
Telephone number	218-739-8407					

A responsible official is defined as a president, vice president, secretary, or treasurer for a corporation; general partner or the proprietor for a partnership; and principal executive officer or ranking elected official for municipal, state, federal or public agency.

#### B. PLANT DESCRIPTION

<ol> <li>Standard Industri</li> </ol>	al Classification Code (SIC	code):			
Primary SIC code:	4911	Secondary SIC co	ode (if applicable):		
P	lease contact the Departme	ent if unable to de	etermine your SIC	code.	
2. Briefly describe t	the operations at the facility,	including raw mat	terials and finished	products:	
Coal Power Plant.	The plant is used to produce	electricity.			
	copy, if available, of any pr ding pollution control devi please attach the ad	ices. If additional	l space is needed t	-	
new source or modi ambient air quality the new source or n	modification to an existing fication will not prevent or i standard. Please attach air d modification will not prevent	nterfere with the a lispersion modeling	ttainment or maint g or other documer	enance of an a its that will de	pplicable monstrate
applicable ambient	air quality standard.				am
	air quality standard. nodeling been conducted (pl	ease check one)?	Yes		No

#### C. COMPLIANCE PLAN

If it is anticipated that a permitted unit will not be operating in compliance at the time of permit issuance, a proposed compliance plan shall be included with the application. The proposed compliance plan shall include a narrative description of the following:

- 1. The requirements (i.e., statutes, air quality rules, permit conditions, etc.) the source is not in compliance with at the time of submittal of this application or permit issuance;
- 2. How the facility intends to bring the unit(s) into compliance; and
- 3. A compliance schedule for when the source will achieve compliance with such requirements;

The compliance schedule must include a statement that progress reports will be submitted at least once every six months and must be at least as stringent as that contained in any judicial consent decree or administrative order to which the applicant is subject.

#### D. MAPS

For stationary sources only, please enclose a map or a drawing showing roadways, location of plant and the nearest residents in each direction from the source. Include other structures, which may be affected.

#### E. AIR QUALITY EMISSIONS SUMMARY

If air quality emissions are available, please complete the following table:

	Actual	Potential Controlled	Potential Uncontrolled
Pollutant	(tons per year)	(tons per year)	(tons per year)
Particulate	See Attached		
Sulfur Dioxide			
Nitrogen Oxide			
Carbon Monoxide			
Volatile Organic Compounds			
Hazardous Air Pollutants (if appl	icable)		,

Remember that potential emissions are calculated assuming that the permitted unit is operated 24 hours per day, 7 days per week, 52 weeks per year at maximum design capacity. Attach all calculations, MSDS sheets for all products containing volatile organic compounds and/or hazardous air pollutants, and other supporting documentation.

Please contact the Department if assistance is needed for calculating emissions for the permitted units such as emission factors, clarifying what potential emissions are, efficiency for control equipment, etc.

#### F. ADDITIONAL FORMS

The following forms must be completed for each piece of specific equipment at the facility and submitted with this form:

Boiler Incinerator Kiln Dryer

Miscellaneous Process Paint Booth Storage Tank

The following forms must be completed for each piece of specific air control equipment at the facility and submitted with this form:

Baghouse Cyclone Electrostatic Precipitator

Miscellaneous Control Thermo Oxidizer Wet Scrubber

#### G. CERTIFICATION OF COMPLIANCE

#### I certify the following:

- 1. The methods such as monitoring, record keeping, reporting, and stack test performance results described within this application shall be used to determine continuous or intermittent compliance;
- 2. A compliance certification document will be submitted to the Department at least annually or at other times designated by the Department for the duration of the permit;
- 3. The source is in compliance and will continue to demonstrate compliance with all applicable requirements, except for those designated in the attached compliance plan (if applicable); and
- 4. This application is submitted in accordance with the provisions of the South Dakota Codified Laws 34A-1 and Administrative Rules of South Dakota 74:36. To the best of my knowledge, after reasonable inquiry, the statements and information contained in the application and supporting documents are true, accurate, and complete. In accordance with South Dakota Codified Laws 1-40-27, I have also enclosed a completed Certification of Applicant form.

Signature:

Print Name:

Terry Graumann

Date

Responsible Official



### CERTIFICATION OF APPLICANT

(please complete shaded areas - if you have questions call (605) 773-3151)

In the Matter of the Application of	Big Stone Power Plant
	(Facility Name)
State of	South Dakota
County of	Grant
I, Terry Graumann	, the applicant in the above matter after being duly
sworn upon oath hereby certify the following i	nformation in regard to this application:

#### South Dakota Codified Laws Section 1-40-27 provides:

"The secretary may reject an application for any permit filed pursuant to Titles 34A or 45, including any application by any concentrated swine feeding operation for authorization to operate under a general permit, upon making a specific finding that:

- (1) The applicant is unsuited or unqualified to perform the obligations of a permit holder based upon a finding that the applicant, any officer, director, partner or resident general manager of the facility for which application has been made:
- (a) Has intentionally misrepresented a material fact in applying for a permit;
- (b) Has been convicted of a felony or other crime involving moral turpitude;
- (c) Has habitually and intentionally violated environmental laws of any state or the United States which have caused significant and material environmental damage;
- (d) Has had any permit revoked under the environmental laws of any state or the United States; or
- (e) Has otherwise demonstrated through clear and convincing evidence of previous actions that the applicant lacks the necessary good character and competency to reliably carry out the obligations imposed by law upon the permit holder; or
- (2) The application substantially duplicates an application by the same applicant denied within the past five years which denial has not been reversed by a court of competent jurisdiction. Nothing in this subdivision may be construed to prohibit an applicant from submitting a new application for a permit previously denied, if the new application represents a good faith attempt by the applicant to correct the deficiencies that served as the basis for the denial in the original application.

All applications filed pursuant to Titles 34A and 45 shall include a certification, sworn to under oath and signed by the applicant, that he is not disqualified by reason of this section from obtaining a permit. In the absence of evidence to the contrary, that certification shall constitute a prima facie showing of the suitability and qualification of the applicant. If at any point in the application review, recommendation or hearing process, the secretary finds the applicant has intentionally made any material misrepresentation of fact in regard to this certification, consideration of the application may be suspended and the application may be rejected as provided for under this section.

Applications rejected pursuant to this section constitute final agency action upon that application and may be appealed to circuit court as provided for under chapter 1-26."

Pursuant to SDCL 1-40-27, I certify that I have read the forgoing provision of state law, and that I am not disqualified by reason of that provision from obtaining the permit for which application has been made.

Dated this	23/12	/day of	Sebruary	, 20	-0607
	May/	Draw-			
		$\mathbf{A}_{\mathbf{l}}$	pplicant (signature)		
Subscribed	and sworn befor	e me this:			
Dated this	23/4	day of	February	, 20	2607
		Hancy	D. Tollerson		
		Note	ary Public (signature)		
My commis	ssion expires:	Jan	ceary 31, 2010		
iviy commis	ssion expires.	Jun	mary 31, 2010		



PLEASE ATTACH SHEET DISCLOSING ALL FACTS PERTAINING TO SDCL 1-40-27 (1) (a) THROUGH (e).
ALL VIOLATIONS MUST BE DISCLOSED, BUT WILL NOT AUTOMATICALLY RESULT IN THE REJECTION OF AN APPLICATION.



### Air Quality Permit Application Form Boiler Turbine or Furnace

## This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler	#1, Unit #1, etc):	13		
2. Manufacturer:	TBD			Manufacture	date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cyc	le combustion to	ırbine, generator	r, etc.)	
Unit II only normal	flow max load				
5. Maximum design	ed operating rate	(name plate):			
	6,000.00	m	nillion Btus per l	nour heat input	
or		h	orsepower with	boiler efficiency	y:
or		k	ilowatts with bo	iler efficiency:	
6. Check the approp	oriate box(es) for	orimary and seco	endary fuels:		
Natural gas			Propane	e	
X Distillate oil		Sulfur content	0.05	Weight percen	t
Residual oil		Sulfur content		Weight percen	t
Bituminous C	Coal X	Subbituminou	is Coal	Ligni	te Coal
Coal sulfur conte	ent 0.80	Weight percer	nt Coal ash co	ontent 9.0	Weight percent
X Other (please	specify) B	io diesel			
7. Has a stack test b	een conducted (cl	neck appropriate	box)?	Yes	X No
If a stack test has be application. If the I most recent stack te	Department alread				report to this e specify the date of
Date of most recent	stack test:				
Control Equipmen	• •		_		9
Baghouse, wet flue	gas desulfurizatio	n, selective cata	lytic reduction		

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

Stack Information: If this application is a renewal, contact the air program. We may have this information.

	feet	695,103.41	meters
	feet	5,019,218.73	meters
1,124	feet		meters
498	feet		meters
34.00	feet		meters
See below	degrees Fahr	enheit	
w Rate:	•		
feet per	second		meters per second
-	and/or		
	498 34.00 See below ow Rate: feet per	feet   feet	feet 5,019,218.73  1,124 feet feet feet  34.00 See below See below w Rate:  feet per second

actual cubic meters per second

Flow Rate: See below actual cubic feet per minute

Parameter	Boiler 1 Only	Boiler 2 Only	Both Boilers
Temperature (F)	138	136	137
Velocity (ft/s)	29.68	33.89	63.57
Flowrate (lb/hr)	6,213,000	6,918,000	13,131,000
Flowrate (acfm)	1,665,000	1,914,000	3,579,000



### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

	Equipment and Processes						
1. Unit 13: Unit II	Boiler only normal flow	max load					
2.							
3.							
4.							
5.							
Manufacturer Infor	mation:						
Manufacturer?	TBD						
Manufacturer date?	TBD	Installation date?	Spring 2008				
Manufacturer's design	ned control efficiency?		%				
Type of baghouse (pl	ease check one)?		•				
Reverse Air	Pulse Jet	Shaker Other (sp	pecify)				
Type of bags?	TBD						
Number of bags?	TBD	Air/cloth ratio? TBl	D				
Baghouse Operation	and Maintenance:						
Pressure drop across	baghouse? TBD in	nches water (minimum)	TBD inches water (maximum)				
Inlet Temperature?	TBD Fahr	renheit (minimum) TBD	Fahrenheit (maximum)				
Outlet Temperature?	Outlet Temperature? TBD Fahrenheit (minimum) TBD Fahrenheit (maximum)						
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):							
Bag changing depend	lent on application and g	rain loading.					

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,103.41	meters
Y- Coordinate or Northing: 1		feet	or	5,019,218.73	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	498	feet	or		meters
Exit Stack Diameter	34.00	feet	or		meters
Exit Stack Temperature	See below	degrees	Fahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	See below feet per second	meters per second
	and/or	
Flow Rate:	See below actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

Parameter	Boiler 1 Only	Boiler 2 Only	Both Boilers
Temperature (F)	138	136	137
Velocity (ft/s)	29.68	33.89	63.57
Flowrate (lb/hr)	6,213,000	6,918,000	13,131,000
Flowrate (acfm)	1,665,000	1,914,000	3,579,000



#### **Air Quality Permit Application**

#### Wet Scrubber Data Sheet

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this wet scrubber (please list all equipment and processes):

	EquipmeE	ent and Processes	
1. Unit 13: Unit II I	Boiler FGD (Flue Gas Desulf	urization)	
2.			
3.			
4.			
5.			
Manufacturer Inform	nation:		int till 1918 gilder all 14 - Newy yng riftering fall Sociae Arek Arek Arek genydd i'i 1918 i 1955 gallaid a s
Manufacturer?	TBD		
Manufacturer date?	TBD	Installation date?	Spring 2008
Manufacturer's design	ed control efficiency?		%
Type of wet scrubber (	(please check one)?		
Venturi	Demister Othe	r (specify)	
Scrubbing Additives?	Limestone		
Wet Scrubber Opera	tion and Maintenance:		
Pressure drop across v	vet scrubber? TBD inches	s water (minimum)	TBD inches water (maximum)
Inlet Temperature?	TBD Fahrenhei	t (minimum) TBD	Fahrenheit (maximum)
Outlet Temperature?	TBD Fahrenhei	t (minimum) TBD	Fahrenheit (maximum)
Water recycled (check	cone)? Yes	No	
If yes, number of pond	d(s): Pond size:	Type of	liner:
If no, describe type of	treatment and location of an	y planned water disc	charge from the property:
Describe maintenance	of wet scrubber (visual inspe	ection, how often no	ands are cleaned, etc.)

Stack Information: If this application is a renewal, contact the air program. We may have this information. X- Coordinate or Easting: 1 695,103.41 feet meters or Y-Coordinate or Northing: 1 feet 5,019,218.73 meters or Base Elevation of Stack: 1 1,124 feet or meters Stack Height: 498 feet or meters 34.00 Exit Stack Diameter feet or meters Exit Stack Temperature See below degrees Fahrenheit Exit Stack Velocity and/or Flow Rate: Velocity: See below feet per second meters per second and/or Flow Rate: See below actual cubic feet per minute actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

Parameter	Boiler 1 Only	Boiler 2 Only	Both Boilers
Temperature (F)	138	136	137
Velocity (ft/s)	29.68	33.89	63.57
Flowrate (lb/hr)	6,213,000	6,918,000	13,131,000
Flowrate (acfm)	1,665,000	1,914,000	3,579,000



### **Air Quality Permit Application Form Miscellaneous Control Device**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

	aneous control device and how it works:					
Coal Fired-Boiler usi powered generator.	ng subbituminous pulverized coal to generate steam to power to a 630 MW steam					
Equipment and pro-	cesses served by this baghouse (please list all equipment and processes):					
Equipment and Processes						
1. Unit 13: Unit II	Boiler SCR (Selective Catalytic Reduction)					
2.						
3.						
4.						
5.						
Manufacturer Infor	mation:					
Manufacturer?	TBD					
Manufacturer date?	TBD Installation date? Spring 2008					
Manufacturer's design	ned control efficiency? %					
Miscellaneous Contr	rol Device Operation and Maintenance:					
Pressure drop across	control unit? TBD Inches water (minimum) TBD inches water (maximum)					
Inlet Temperature?	TBD Fahrenheit (minimum) TBD Fahrenheit (maximum)					
Outlet Temperature?	TBD Fahrenheit (minimum) TBD Fahrenheit (maximum)					
Describe maintenance	e of control unit (use of visual inspections, maintenance schedule, etc.):					

<b>Stack Information:</b> If this application is a renewal, contact the air program. We may have this information.							
V. Coordinate on Footings 1		G4		605 102 41	1		
X- Coordinate or Easting: 1		feet	or	695,103.41	meters		
Y- Coordinate or Northing: 1		feet	or	5,019,218.73	meters		
Base Elevation of Stack: 1	1,124	feet	or		meters		
Stack Height:	498	feet	or		meters		
Exit Stack Diameter	34.00	feet	or		meters		
Exit Stack Temperature	See below	degrees Fahrenheit					
Exit Stack Velocity and/or Flow Rate:							
Velocity: See below feet per second meters per second							
and/or							
Flow Rate: See below actual cubic feet per minute actual cubic meters per second							
<sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories							

information in these categories.

Parameter	Boiler 1 Only	Boiler 2 Only	Both Boilers
Temperature (F)	138	136	137
Velocity (ft/s)	29.68	33.89	63.57
Flowrate (lb/hr)	6,213,000	6,918,000	13,131,000
Flowrate (acfm)	1,665,000	1,914,000	3,579,000



# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boile	er #1, Unit #1, etc):	14					
2. Manufacturer:	TBD				Manufa	acture d	ate:	
3. Model number:	TBD							
4. Type (i.e., steam	boiler, simple c	ycle combustion to	ırbine,	generato	r, etc.)		-	
Emergency Fire Wa	ıter Pump – BSI	РП						
5. Maximum design	ed operating ra	te (name plate):			_			
					million	Btus pe	er hour h	eat input
or		420			horsep	ower		
or					kilowa	tts		
6. Check the approp	oriate box(es) for	or primary and seco	ndary f	uels:	_			
Natural gas				Propan	e			
X Distillate oil		Sulfur content	0.015		Weight	percent		
Residual oil		Sulfur content			Weight	percent		
Bituminous (	Coal	Subbituminou	s Coal			Lignite	e Coal	
Coal sulfur cont	ent	Weight percer	nt Co	al ash co	ontent		Weigh	t percent
X Other (please	specify)	Bio diesel						
7. Has a stack test b	een conducted	(check appropriate	box)?		Yes	3	X	No
If a stack test has lapplication. If the lamost recent stack te	Department alre							
Date of most recent	stack test:			777,47618				
Control Equipment cyclone, wet scrubb								

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting: feet 695,645 meters Y- Coordinate or Northing: feet 5,019,225.50 meters Base Elevation of Stack: 1,124 feet meters Stack Height: 15.00 feet meters **Exit Stack Diameter** 0.83 feet meters **Exit Stack Temperature** 904.00 degrees Fahrenheit Exit Stack Velocity and/or Flow Rate: Velocity: 76.58 feet per second meters per second and/or Flow Rate: 2,486.2 actual cubic feet per minute actual cubic meters per second

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



## This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler#	1, Unit #1, etc):	15		
2. Manufacturer:	TBD			Manufacture d	late:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cycl	e combustion to	ırbine, generato	r, etc.)	<u> </u>
Emergency Diesel C	Generator - BSP II				
5. Maximum design	ed operating rate (	name plate):		<b></b>	
				million Btus p	er hour heat input
or	2	2,220		horsepower	
or				kilowatts	
6. Check the approp	riate box(es) for p	rimary and seco	ondary fuels:	-	
Natural gas			Propan	e	
X Distillate oil		Sulfur content	0.015	Weight percent	
Residual oil		Sulfur content		Weight percent	
Bituminous C	oal	Subbituminou	is Coal	Lignit	e Coal
Coal sulfur conte	ent	Weight percer	nt Coal ash co	ontent	Weight percent
X Other (please	specify) Bi	o diesel			
7. Has a stack test be	een conducted (ch	eck appropriate	box)?	Yes	X No
If a stack test has be application. If the I most recent stack te	Department already				
Date of most recent	stack test:				
Control Equipmen cyclone, wet scrubb		^ <u>-</u>			<b>O</b> /

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting: feet 695,329 meters Y- Coordinate or Northing: 5,019,197 feet meters Base Elevation of Stack: 1,124 feet meters Stack Height: 15.00 feet meters **Exit Stack Diameter** 1.50 feet meters Exit Stack Temperature 900.00 degrees Fahrenheit Exit Stack Velocity and/or Flow Rate: Velocity: 100.44 feet per second meters per second and/or Flow Rate: 10,650.00 actual cubic feet per minute actual cubic meters per second

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identification (i.e., Boiler #1, Unit #1,	etc): 16
2. Manufacturer: TBD	Manufacture date:
3. Model number: TBD	
4. Type (i.e., steam boiler, simple cycle combusti	on turbine, generator, etc.)
Cooling Tower (18 Cells)	and the second of the second o
5. Maximum designed operating rate (name plate	<u>:</u>
312,540.00 gallons per r	ninute million Btus per hour heat input
or	horsepower
or	kilowatts
6. Check the appropriate box(es) for primary and	secondary fuels:
Natural gas	Propane
Distillate oil Sulfur con	ent Weight percent
Residual oil Sulfur con	ent Weight percent
Bituminous Coal Subbitum	nous Coal Lignite Coal
Coal sulfur content Weight p	rcent   Coal ash content   Weight percent
Other (please specify)	
7. Has a stack test been conducted (check approp	iate box)? Yes X No
If a stack test has been conducted, please attach application. If the Department already has a copy most recent stack test.	a copy of the most recent stack test report to this of the most recent stack test, please specify the date of
Date of most recent stack test:	
Control Equipment: If applicable, types of air p cyclone, wet scrubber, electrostatic precipitator,	ollution control equipment (Examples: baghouse, nermal oxidizer, miscellaneous control device, etc.).
0.0005% drift eliminators	

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting:		feet	See below	meters
Y- Coordinate or Northing:		feet	See below	meters
Base Elevation of Stack:	1,124 (per cell)	feet		meters
Stack Height:	60.00 (per cell)	feet		meters
Exit Stack Diameter	33.00 (per cell)	feet		meters
Exit Stack Temperature	61.00 (per cell)	degrees I	Fahrenheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	39.60 (per cell) feet per second	meters per second
	and/or	
Flow Rate:	2,032,189 actual cubic feet per minute (per cell)	actual cubic meters per second

Cooling Tower's X/Y Coordinates (in UTM meters)

	`	•
X	Y	
695497.63	5018875.00	
695502.75	5018863.00	
695507.81	5018850.00	
695513.63	5018835.50	
695519.69	5018824.00	
695525.94	5018809.50	
695534.44	5018795.00	
695539.75	5018781.50	
695546.88	5018768.50	
695517.44	5018884.50	
695522.81	5018873.00	
695529.31	5018858.00	
695537.38	5018845.50	
695542.75	5018834.00	
695549.44	5018820.50	
695555.38	5018806.00	
695561.31	5018793.50	
695567.75	5018778.00	



#### This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit.

(please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler	#1, Unit #1, etc):	17		
2. Manufacturer:	TBD			Manufacture	e date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cy	cle combustion tu	rbine, generato	r, etc.)	
Coal Reclaim Syste	m				
5. Maximum design	ed operating rate	e (name plate):			
				million Btus	per hour heat input
or				horsepower	
or				kilowatts	
6. Check the approp	oriate box(es) for	primary and seco	ndary fuels:		
Natural gas			Propan	e	
Distillate oil		Sulfur content		Weight perce	ent
Residual oil		Sulfur content		Weight perce	nt
Bituminous C	Coal	Subbituminou	s Coal	Lign	nite Coal
Coal sulfur conte	ent	Weight percer	t Coal ash co	ontent	Weight percent
Other (please	specify)				
7. Has a stack test b	een conducted (	check appropriate	box)?	Yes	X No
If a stack test has be application. If the I most recent stack te	Department alrea				st report to this use specify the date of
Date of most recent	stack test:				
Control Equipmen					
Baghouse					
Please complete	a tha annranria	te air quality nor	mit applicatio	n form for oa	ch type of control

equipment that controls air emissions from this operation.

Misc Process Form

X- Coordinate or Easting: feet 695,052.19 meters Y- Coordinate or Northing: feet 5,019,408.00 meters 1,124 Base Elevation of Stack: feet meters Stack Height: 20 feet meters **Exit Stack Diameter** 1.50 feet meters Exit Stack Temperature Ambient degrees Fahrenheit Exit Stack Velocity and/or Flow Rate: Velocity: 63.66 feet per second meters per second and/or Flow Rate: 6,750.00 Actual cubic feet per actual cubic meters per second

minute

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

**Equipment and Processes** 

Equipment and processes served by this baghouse (please list all equipment and processes):

I. Unit 17: Coal R	eclaim System			
2.				
3.				
4.				
5.				
Manufacturer Infor	mation:			2.X. 1971.11. 2022 20.25;53.000 1117.5. 111 <u>911.000 1111115500</u>
Manufacturer?	TBD			
Manufacturer date?	TBD	Installation d	late? Sprin	g 2008
Manufacturer's design	ned control efficiency?	0.01 gr/dscf	%	
Type of baghouse (pl	lease check one)?			
Reverse Air	X Pulse Jet	Shaker Ot	her (specify)	
Type of bags?	TBD			
Number of bags?	TBD	Air/cloth ratio?	TBD	
Baghouse Operation	n and Maintenance:	-		
Pressure drop across	baghouse? TBD i	inches water (minim	um) TBD	inches water (maximum)
Inlet Temperature?	Ambient Fah	nrenheit (minimum)	Ambient	Fahrenheit (maximum)
Outlet Temperature?	Ambient Fah	nrenheit (minimum)	Ambient	Fahrenheit (maximum)
Describe maintenance	e of baghouse (use of d	ye test, visual inspec	tions, changing	ng bag frequency, etc.):
Bag changing depend	lent on application and	grain loading.		
	AAA			***************************************

X- Coordinate or Easting: 1		feet	or	695,052.19	meters
Y- Coordinate or Northing: 1		feet	or	5,019,408.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	20	feet	or		meters
Exit Stack Diameter	1.50	feet	or		meters
Exit Stack Temperature	Ambient	degrees	Fahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	63.66 feet per second	meters per second
	and/or	
Flow Rate:	6,750.00 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested **Stack Information:** If this application is a renewal, contact the air program. We may have this information.



## This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

				**************************************
1. Facility identification	on (i.e., Boiler #1, Unit #1, etc):	20		
2. Manufacturer:	TBD		Manufacture of	date:
3. Model number:	TBD			
4. Type (i.e., steam bo	oiler, simple cycle combustion tur	bine, generato	r, etc.)	
Limestone Reclaim Sy	ystem			
5. Maximum designed	l operating rate (name plate):			
			million Btus p	er hour heat input
or			horsepower	
or			kilowatts	
6. Check the appropria	ate box(es) for primary and secon	dary fuels:	_	
Natural gas	- · ·	Propan	e	
Distillate oil	Sulfur content		Weight percent	t
Residual oil	Sulfur content		Weight percent	t
Bituminous Coa	al Subbituminous	Coal	Ligni	te Coal
Coal sulfur content	t Weight percent	Coal ash co	ontent	Weight percent
Other (please sp	pecify)			
7. Has a stack test bee	en conducted (check appropriate b	ox)?	Yes	X No
	en conducted, please attach a copy partment already has a copy of the			
Date of most recent sta	ack test:			
	If applicable, types of air pollution, electrostatic precipitator, therma			
Baghouse				

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

**Baghouse Application Form** 

X- Coordinate or Easting:		feet	695,071.88	meters		
Y- Coordinate or Northing:		feet	5,019,152.50	meters		
Base Elevation of Stack:	1,124	feet		meters		
Stack Height:	20.00	feet		meters		
Exit Stack Diameter	1.50	feet		meters		
Exit Stack Temperature	Ambient degrees Fahrenheit					
Exit Stack Velocity and/or Flo	ow Rate:					
Velocity:	56.59 feet per	second		meters per second		
and/or						
Flow Rate: 6,000.00	actual cubic feet per	minute	actual cubi	c meters per second		

information.



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

	Edaiha	ent and Processes	
1. Unit 20: Limesto	one Reclaim System		
2.			
3.			
4.			
5.			
Manufacturer Infor	mation:		
Manufacturer?	TBD		
Manufacturer date?	TBD	Installation date?	Spring 2008
Manufacturer's design	ned control efficiency? 0.0	l gr/dscf	%
Type of baghouse (pl	ease check one)?		
Reverse Air	X Pulse Jet Shak	cer Other (sp	pecify)
Type of bags?	TBD		
Number of bags?	TBD Air/o	cloth ratio? TB	D
Baghouse Operation	and Maintenance:		
Pressure drop across	baghouse? TBD inches	water (minimum)	TBD inches water (maximum)
Inlet Temperature?	Ambient Fahrenhei	it (minimum) Amb	ient Fahrenheit (maximum)
$Outlet\ Temperature?$	Ambient Fahrenhei	it (minimum) Amb	pient Fahrenheit (maximum)
Describe maintenance	e of baghouse (use of dye test	, visual inspections,	changing bag frequency, etc.):
Bag changing depend	lent on application and grain l	loading.	

X- Coordinate or Easting: 1		feet	or	695,071.88	meters
Y- Coordinate or Northing: 1		feet	or	5,019,152.50	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	20.00	feet	or		meters
Exit Stack Diameter	1.50	feet	or		meters
Exit Stack Temperature	Ambient	degrees I	ahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	56.59 feet per second	neters per second
	and/or	
Flow Rate:	6,000.00 actual cubic feet per minut	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

						79 - 1 0 2 1 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0
1. Facility identifies	ation (i.e., Boiler	#1, Unit #1, etc):	21			
2. Manufacturer:	TBD			Manufactur	re date:	
3. Model number:	TBD					
4. Type (i.e., steam	boiler, simple cyc	cle combustion tu	rbine, genera	ator, etc.)		
Limestone Receiving	ng System					
5. Maximum design	ned operating rate	(name plate):				
				million Btu	s per hour	heat input
or				horsepower	•	
or				kilowatts		
6. Check the approp	priate box(es) for	primary and seco	ndary fuels:			
Natural gas			Prop	oane		
Distillate oil		Sulfur content	<u> </u>	Weight perc	ent	
Residual oil		Sulfur content		Weight perc		
Bituminous C	Coal	Subbituminou	s Coal	in the second se	mite Coal	
Coal sulfur conte		Weight percen	1	[secondorates ] -	- 	ht percent
Other (please	1:500	18 p	.   0001 151		114-5	no posoone
7. Has a stack test b	2 2	heck appropriate	hox)?	Yes	$T_{X}$	No
	`			*****	0.0000000000	
If a stack test has tapplication. If the I						
most recent stack te		ly has a copy of the	ne most rece	nt stack test, pre	ase specify	r the date of
Date of most recent	t stack test:					
	222 (223 (223 (223 (223 (223 (223 (223	0.000.00000000000000000000000000000000		<u> </u>		
Control Equipmen	ıt: If applicable, t	ypes of air pollut	ion control e	quipment (Exan	ıples: bagh	iouse,
cyclone, wet scrubb	er, electrostatic p	recipitator, therm	al oxidizer,	miscellaneous co	ontrol devi	ce, etc.).
D. A.						
Baghouse				• -	_	
Please complet	te the appropriat	e air quality per	mit applica	tion form for ea	ich type of	f control

equipment that controls air emissions from this operation.

X- Coordinate o	r Easting:		feet	(	695,022.56	meters	
Y- Coordinate o	r Northing:		feet	5,0	019,074.00	meters	
Base Elevation of	of Stack:	1,124	feet			meters	
Stack Height:		20.00	feet			meters	
Exit Stack Diam	eter	1.40	feet			meters	
Exit Stack Temp	perature	Ambient degrees Fahrenheit					
Exit Stack Veloc	city and/or Flo	ow Rate:	_				
Velocity:		54.13 feet pe	r second			meters per second	
and/or							
Flow Rate:	5,000.00	actual cubic feet po	er minute		actual cubic	c meters per second	



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

				Equ	uipme	nt and Pr	ocesses	_		
1.	Unit 21: Limest	tone R	eceiving Sy	stem						ohr- Silvi
2.										
3.										
4.										
5.										
Mai	iufacturer Infoi	rmatic	on:							
Mar	ufacturer?	TBL	)							
Mar	ufacturer date?	TBI	)			Installation	on date?	Spring	2008	
Mar	ufacturer's desig	med co	ontrol effici	ency?	0.01	gr/dscf		%		
Тур	e of baghouse (p	lease o	check one)?					•		
	Reverse Air	X	Pulse Jet		Shak	er	Other (sp	pecify)		
Тур	e of bags?		TBD							
Nun	nber of bags?		TBD		Air/c	loth ratio?	TB	D		
Bag	house Operation	n and	Maintenar	ice:				-		
Pres	sure drop across	bagho	ouse? TB	D ii	nches	water (mir	nimum)	TBD	inches water (maximum	ı)
Inle	Temperature?		Ambient	Fahr	enhei	t (minimu	m) Amb	ient	Fahrenheit (maximum)	
Out	et Temperature?	Am	nbient	Fahı	enhei	t (minimu	m) Amb	oient	Fahrenheit (maximum)	
Des	cribe maintenanc	e of b	aghouse (us	e of dy	e test,	visual ins	spections,	changing	g bag frequency, etc.):	
Bag	changing depend	dent o	n applicatio	n and g	grain l	oading.				

X- Coordinate or Easting: 1		feet	or	695,022.56	meters
Y- Coordinate or Northing: 1		feet	or	5,019,074.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	20.00	feet	or		meters
Exit Stack Diameter	1.40	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fa	hre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	54.13 feet per second	meters per second
	and/or	
Flow Rate:	5,000.00 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



## This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler	#1, Unit #1, etc):	22		
2. Manufacturer:	TBD			Manufacture	date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cyc	ele combustion tu	ırbine, generato	r, etc.)	
Coal Tripper/Silo Fi	ill System	77.8			
5. Maximum design	ed operating rate	(name plate):		_	
				million Btus	per hour heat input
or				horsepower	
or				kilowatts	
6. Check the approp	oriate box(es) for	primary and seco	ndary fuels:	_	
Natural gas			Propan	e	
Distillate oil		Sulfur content		Weight percer	nt
Residual oil		Sulfur content		Weight percer	nt
Bituminous C	Coal	Subbituminou	s Coal	Lign	ite Coal
Coal sulfur conte	ent	Weight percer	nt Coal ash co	ontent	Weight percent
Other (please	specify)				
7. Has a stack test b	een conducted (c	heck appropriate	box)?	Yes	X No
If a stack test has be application. If the I most recent stack te	Department alread				report to this se specify the date of
Date of most recent	stack test:				
Control Equipmen cyclone, wet scrubb					
Baghouse					
D)	. 11				

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting:	1	feet 6	95,299.00 meters				
Y- Coordinate or Northing:	1	feet 5,0	019,273.00 meters				
Base Elevation of Stack:	1,124	feet	meters				
Stack Height:	279.00	feet	meters				
Exit Stack Diameter	3.75	feet	meters				
Exit Stack Temperature	tack Temperature Ambient degrees Fahrenheit						
Exit Stack Velocity and/or Flo	ow Rate:						
Velocity:	53.57 feet per se	econd	meters per second				
and/or							
Flow Rate: 35,500.00	actual cubic feet per r	minute	actual cubic meters per second				

information.



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

		Equipment a	nd Processes		
1. Unit 22: Coal Tr	ipper/Silo Fill Sys	tem			
2.					
3.					
4.					
5.					
Manufacturer Inform	nation:				***************************************
Manufacturer?	TBD				
Manufacturer date?	TBD	Inst	allation date?	Spring 2008	
Manufacturer's design	ed control efficien	ncy? 0.01 gr/d	scf	%	
Type of baghouse (ple	ease check one)?	<u></u>		1	
Reverse Air	X Pulse Jet	Shaker	Other (sp	pecify)	
Type of bags?	TBD				
Number of bags?	TBD	Air/cloth	ratio? TBI	O	
Baghouse Operation	and Maintenance	e:	<u>-</u>		
Pressure drop across b	paghouse? TBD	inches wate	r (minimum)	TBD inches wa	ter (maximum)
Inlet Temperature?	Ambient	Fahrenheit (mi	nimum) Amb	ient Fahrenhe	it (maximum)
Outlet Temperature?	Ambient	Fahrenheit (mi	nimum) Amb	ient Fahrenhe	it (maximum)
Describe maintenance	of baghouse (use	of dye test, visu	al inspections,	changing bag frequ	ency, etc.):
Bag changing depende	ent on application	and grain loadir	ıg.		

X- Coordinate or Easting: 1		feet	or	695,299.00	meters
Y- Coordinate or Northing: 1		feet	or	5,019,273.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	279.00	feet	or		meters
Exit Stack Diameter	3.75	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fa	ahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	53.57 feet per second	meters per second
	and/or	
Flow Rate:	35,500.00 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identification	ation (i.e., Boiler	#1, Unit #1, etc):	23		
2. Manufacturer:	TBD			Manufacture	date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cy	cle combustion tu	rbine, generato	r, etc.)	
Fly ash silo bin ven	t				
5. Maximum design	ned operating rate	(name plate):		_	
				million Btus	per hour heat input
or		horsepower			
or				kilowatts	
6. Check the approp	oriate box(es) for	primary and seco	ndary fuels:	-	
Natural gas			Propan	e	
Distillate oil Sulfur content				Weight percer	nt
Residual oil		Sulfur content		Weight percer	nt
Bituminous C	Coal	Subbituminou	s Coal	Lign	ite Coal
Coal sulfur cont	ent	Weight percen	t Coal ash co	ontent	Weight percent
Other (please	specify)				
7. Has a stack test b	een conducted (c	heck appropriate	box)?	Yes	X No
If a stack test has application. If the I most recent stack te	Department alread				report to this se specify the date of
Date of most recent	stack test:				
Control Equipment cyclone, wet scrubb			-		-
Baghouse					
Please complet	e the appropriat	te air quality per	mit applicatio	n form for eac	h type of control

equipment that controls air emissions from this operation.

**Baghouse Application Form** 

X- Coordinate or	Easting:			feet		695,217.63	meters
Y- Coordinate or	Northing:			feet	5,0	019,237.50	meters
Base Elevation of	f Stack:		1,124	feet			meters
Stack Height:			105	feet			meters
Exit Stack Diame	ter		1.9	feet			meters
Exit Stack Temperature Amb			nbient	degrees	Fahrenheit		
Exit Stack Veloci	ity and/or F	low Rate:					
Velocity:		52.90	feet per s	second			meters per second
			a	nd/or			
Flow Rate: 9,	000.00	actual cubic	feet per	minute		actual cubic	meters per second

information.



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

Equipment and Processes					
1. Unit 23: Fly ash silo bin vent					
2.					
3.					
4.					
5.					
Manufacturer Information:					
Manufacturer? TBD					
Manufacturer date? TBD Installation date? Spring 2008					
Manufacturer's designed control efficiency? 0.01 gr/dscf %					
Type of baghouse (please check one)?					
Reverse Air X Pulse Jet Shaker Other (specify)					
Type of bags? TBD					
Number of bags? TBD Air/cloth ratio? TBD					
Baghouse Operation and Maintenance:					
Pressure drop across baghouse? TBD inches water (minimum) TBD inches water (maximum)					
Inlet Temperature? Ambient Fahrenheit (minimum) Ambient Fahrenheit (maximum)					
Outlet Temperature? Ambient Fahrenheit (minimum) Ambient Fahrenheit (maximum)					
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):					
Bag changing dependent on application and grain loading.					

X- Coordinate or Easting: 1		feet or	695,217.63	meters		
Y- Coordinate or Northing: 1		feet or	5,019,237.50	meters		
Base Elevation of Stack: 1	1,124	feet or		meters		
Stack Height:	105	feet or		meters		
Exit Stack Diameter	1.9	feet or		meters		
Exit Stack Temperature	Ambient	degrees Fahre	enheit	•		
Exit Stack Velocity and/or Flow Rate:						

Velocity:	52.90 feet per second	meters per second
	and/or	
Flow Rate:	9,000.00 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



### Air Quality Permit Application Form

#### **Miscellaneous Process**

#### This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler #1,	Unit #1, etc):	24			
2. Manufacturer:	TBD			Manufactur	e date:	
3. Model number:	TBD					
4. Type (i.e., steam	boiler, simple cycle of	combustion tu	rbine, generato	r, etc.)		
Limestone Day Bins	s Vent					
5. Maximum design	ned operating rate (na	me plate):		<b>-1</b>		
				million Btus	s per hour h	eat input
or	or					
or				kilowatts		
6. Check the approp	oriate box(es) for prin	nary and seco	ndary fuels:	_		
Natural gas			Propan	e		
Distillate oil	Su	lfur content		Weight perce	ent	
Residual oil	Su	Ifur content		Weight percent		
Bituminous C	Coal S	Subbituminou	s Coal	Lig	nite Coal	
Coal sulfur conte	ent V	Weight percer	nt Coal ash co	ontent	Weight	percent
Other (please	specify)					
7. Has a stack test b	een conducted (check	k appropriate	box)?	Yes	X	No
	peen conducted, pleas Department already hest.					
Date of most recent	stack test:					
	at: If applicable, types per, electrostatic preci					
Baghouse						
Please complet	e the appropriate ai	r quality per	mit application	n form for ea	ch type of c	control

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting:		feet	695,149.56	meters		
Y- Coordinate or Northing:		feet	5,019,202.00	meters		
Base Elevation of Stack:	1,124	feet		meters		
Stack Height:	128.00	feet		meters		
Exit Stack Diameter	1.33	feet		meters		
Exit Stack Temperature	Ambient	degrees Fahrenheit				
Exit Stack Velocity and/or Flo	ow Rate:					
Velocity:	0.33* feet per	second		meters per second		
		and/or				
Flow Rate: 3,281	actual cubic feet per	minute	actual cubi	c meters per second		
*obstructed or horizontal disc	harge	<u> </u>				

information.



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

	Eg	uipment and Pro	cesses			
1. Unit 24: Limesto	one Day Bins Vent					
2.						
3.						
4.						
5.						
Manufacturer Inform	mation:					
Manufacturer?	TBD					
Manufacturer date?	TBD	Installation	date?	Spring	2008	
Manufacturer's design	ned control efficiency?	0.01 gr/dscf		%		
Type of baghouse (ple	ease check one)?			!		
Reverse Air	X Pulse Jet	Shaker C	Other (sp	ecify)		
Type of bags?	TBD					
Number of bags?	TBD	Air/cloth ratio?	TBI	)		
Baghouse Operation	and Maintenance:					
Pressure drop across b	oaghouse? TBD i	nches water (minir	num)	TBD	inches water (maximum)	
Inlet Temperature?	Ambient Fah	renheit (minimum)	) Amb	ient	Fahrenheit (maximum)	
Outlet Temperature?	Ambient Fah	renheit (minimum)	) Amb	ient	Fahrenheit (maximum)	
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):						
Bag changing dependent on application and grain loading.						

X- Coordinate or Easting: 1		feet	or	695,149.56	meters
Y- Coordinate or Northing: 1		feet	or	5,019,202.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	128.00	feet	or		meters
Exit Stack Diameter	1.33	feet	or		meters
Exit Stack Temperature	Ambient	degrees F	ahre	enheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	0.33* feet per second	meters per second
	and/or	
Flow Rate:	3,281 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

<sup>\*</sup>obstructed or horizontal discharge



#### This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	tion (i.e., Boiler #1, Unit #1, etc):	25					
2. Manufacturer:	TBD		Manufacture d	late:			
3. Model number:	3. Model number: TBD						
4. Type (i.e., steam l	boiler, simple cycle combustion tu	rbine, generato	r, etc.)				
Diesel FW Booster 1	Pump (Boiler)						
5. Maximum designe	ed operating rate (name plate):		<b>-</b>				
			million Btus p	er hour heat input			
or	225.00		horsepower				
or			kilowatts				
6. Check the appropr	riate box(es) for primary and seco	ndary fuels:	_				
Natural gas		Propan	e				
X Distillate oil	Sulfur content	0.015	Weight percent				
Residual oil	Sulfur content		Weight percent				
Bituminous C	oal Subbituminou	s Coal	Lignit	e Coal			
Coal sulfur conte	ent Weight percer	nt Coal ash co	ontent	Weight percent			
X Other (please	specify) Bio diesel						
7. Has a stack test be	een conducted (check appropriate	box)?	Yes	X No			
	een conducted, please attach a copepartment already has a copy of total.						
Date of most recent	stack test:						
- <b>-</b>	t: If applicable, types of air pollut er, electrostatic precipitator, therm	-					
		<u> </u>					

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting:		feet	695,265.44	meters
Y- Coordinate or Northing:		feet	5,019,234.00	meters
Base Elevation of Stack:	1,124	feet		meters
Stack Height:	11.00	feet		meters
Exit Stack Diameter	0.67	feet		meters
Exit Stack Temperature	749.00	degrees Fa	hrenheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	55.76 feet per second	meters per second				
and/or						
Flow Rate:	1,179.5 actual cubic feet per minute	actual cubic meters per second				



# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler #1, Unit #1, etc):	26		
2. Manufacturer:	TBD		Manufacture da	te:
3. Model number:	TBD			
4. Type (i.e., steam	boiler, simple cycle combustion tu	rbine, generato	r, etc.)	
Coal Plant Transfer				
5. Maximum design	ned operating rate (name plate):		<del></del>	
			million Btus per	r hour heat input
or			horsepower	
or			kilowatts	
6. Check the approp	priate box(es) for primary and seco	ndary fuels:		
Natural gas		Propan	e	
Distillate oil	Sulfur content		Weight percent	
Residual oil	Sulfur content		Weight percent	
Bituminous C	Coal Subbituminou	s Coal	Lignite	Coal
Coal sulfur conte	ent Weight percen	t Coal ash co	ontent	Weight percent
Other (please	specify)			
7. Has a stack test be	peen conducted (check appropriate	box)?	Yes	X No
	been conducted, please attach a cop Department already has a copy of the est.			
Date of most recent	stack test:			
	at: If applicable, types of air pollution, electrostatic precipitator, therm			
Baghouse				
Please complete	a the appropriate air quality por	mit applicatio	n form for each t	Time of control

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

information.	**	•	1 0	•		
X- Coordinate or Easting:		feet	69.	5,048.75	meters	
Y- Coordinate or Northing:		feet	5,019	9,459.50	meters	
Base Elevation of Stack:	1,124	feet			meters	
Stack Height:	20.00	feet			meters	
Exit Stack Diameter	1.27	feet			meters	
Exit Stack Temperature Ambient degrees Fahrenheit						
Exit Stack Velocity and/or Flow Rate:						
Velocity:	59.21 feet per	second			meters per second	
and/or						
Flow Rate: 4,500.00	actual cubic feet per	· minute	a	ctual cubic	meters per second	



#### **Air Quality Permit Application**

#### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

			Eq.	<u>uipme</u>	ent and Pi	ocesse	es		
1. Unit 26: Coal Pl	lant T	ransfer Sys	tem						
2.	100 M M M 100 M	18. 45. 11. 11. 11. 12. 12. 12. 12. 12. 12. 12							
3.									
4.									
5.							200 200 200 200 200 200 200 200 200 200		
Manufacturer Infor	matic	on:							
Manufacturer?	TBI	)							
Manufacturer date?	TBI	)		00000000	Installati	on date	e?	Spring	2008
Manufacturer's design	ned co	ontrol effici	ency?	0.01	gr/dscf		00000000 200000000 2000000000	%	
Type of baghouse (pl	ease o	check one)?	•						
Reverse Air	X	Pulse Jet		Shak	er	Other	r (sp	ecify)	
Type of bags?		ŢBD							
Number of bags?		TBD		Air/c	loth ratio?	, [7	TBE	)	
Baghouse Operation and Maintenance:									
Pressure drop across baghouse? TBD inches water (minimum) TBD inches water (maximum)									
Inlet Temperature?	nlet Temperature? Ambient Fahrenheit (minimum) Ambient Fahrenheit (maximum)								
Outlet Temperature? Ambient Fahrenheit (minimum) Ambient Fahrenheit (maximum)									
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):									
Bag changing dependent on application and grain loading.									

X- Coordinate or Easting: 1		feet	or	695,048.75	meters
Y- Coordinate or Northing: 1		feet	or	5,019,459.50	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	20.00	feet	or		meters
Exit Stack Diameter	1.27	feet	or		meters
Exit Stack Temperature	Ambient	degrees l	Fahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	59.21 feet per second	meters per second
	and/or	
Flow Rate:	4,500.00 actual cubic feet per minute	actual cubic meters per second

 $<sup>^{1}</sup>$  - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



### Air Quality Permit Application Form

#### **Miscellaneous Process**

## This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identification (i.e., Boiler #1, Unit #1, etc): 27						
2. Manufacturer: TBD	Manufacture date:					
3. Model number: TBD						
4. Type (i.e., steam boiler, simple cycle combu	ustion turbine, generator, etc.)					
Coal Crusher Building – BSP II						
5. Maximum designed operating rate (name pla	ate):					
	million Btus per hour heat input					
or	horsepower					
or	kilowatts					
6. Check the appropriate box(es) for primary a	and secondary fuels:					
Natural gas	Propane					
Distillate oil Sulfur c	content Weight percent					
Residual oil Sulfur c	content Weight percent					
Bituminous Coal Subbit	tuminous Coal Lignite Coal					
Coal sulfur content Weigh	at percent   Coal ash content   Weight percent					
Other (please specify)						
7. Has a stack test been conducted (check appr	ropriate box)? Yes X No					
· •	ach a copy of the most recent stack test report to this opy of the most recent stack test, please specify the date of					
Date of most recent stack test:						
Control Equipment: If applicable, types of air pollution control equipment (Examples: baghouse, cyclone, wet scrubber, electrostatic precipitator, thermal oxidizer, miscellaneous control device, etc.).						
Baghouse						

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

X- Coordinate or Easting: 695,099.38 feet meters 5,019,452.50 Y- Coordinate or Northing: feet meters Base Elevation of Stack: 1,124 feet meters Stack Height: 95.00 feet meters **Exit Stack Diameter** 2.30 feet meters Exit Stack Temperature Ambient degrees Fahrenheit Exit Stack Velocity and/or Flow Rate: Velocity: 60.17 feet per second meters per second and/or Flow Rate: 15,000 actual cubic feet per minute actual cubic meters per second

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



### **Air Quality Permit Application**

### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

			Equipm	ent and Pr	ocesses		
1. Unit 27: Coal Cr	ushei	r Building – 1	BSP II				
2.							
3.							
4.	<u> 2000,000,000</u> 1888,0086 888,008					80 80 80	
5.							
Manufacturer Inform	 natio	on:					
Manufacturer?	TBD	)					
Manufacturer date?	TBD	)		Installatio	on date?	Spring	2008
Manufacturer's design	ed co	ontrol efficie	ncy? 0.0	l gr/dscf		%	
Type of baghouse (ple	ase c	heck one)?	<u></u>			•	
Reverse Air	X	Pulse Jet	Shak	er	Other (sp	ecify)	
Type of bags?		TBD					
Number of bags?		TBD	Air/o	oloth ratio?	TBI	D	
Baghouse Operation	and	Maintenanc	ee:		<u></u>		
Pressure drop across b	agho	ouse? TBD	inches	water (mir	nimum)	TBD	inches water (maximum)
Inlet Temperature?		Ambient	Fahrenhe	it (minimu	n) Amb	ient	Fahrenheit (maximum)
Outlet Temperature?	Am	ibient	Fahrenhe	it (minimuı	m) Amb	ient	Fahrenheit (maximum)
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):							
Bag changing depende	nt or	n application	and grain	loading.			

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,099.38	meters
Y- Coordinate or Northing: 1		feet	or	5,019,452.50	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	95.00	feet	or		meters
Exit Stack Diameter	2.30	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fahrenheit			

Exit Stack Velocity and/or Flow Rate:

Velocity:	60.17 feet per second	meters per second
	and/or	
Flow Rate:	15,000 actual cubic feet per minute	actual cubic meters per second

 $<sup>^{1}</sup>$  - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



### Air Quality Permit Application Form Miscellaneous Process

# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler	#1, Unit #1, etc):	29				
2. Manufacturer:	TBD			Manufacture	date:		
3. Model number:	TBD						
4. Type (i.e., steam	boiler, simple cy	cle combustion to	ırbine, generato	r, etc.)			
Limestone Precrush	er Building						
5. Maximum design	ed operating rate	(name plate):		_			
				million Btus	per hour	heat input	
or				horsepower			
or				kilowatts			
6. Check the approp	oriate box(es) for	primary and seco	ndary fuels:	_			
Natural gas			Propan	e			
Distillate oil		Sulfur content	Weight percent				
Residual oil		Sulfur content		Weight percent			
Bituminous C	Coal	Subbituminou	s Coal	Lign	ite Coal		
Coal sulfur conte	ent	Weight percer	nt Coal ash co	ontent	Weigl	nt percent	
Other (please	specify)	3					
7. Has a stack test b	een conducted (c	heck appropriate	box)?	Yes	X	No	
If a stack test has be application. If the I most recent stack te	Department alread						
Date of most recent	stack test:	2002_05_0000000000000000000000000000000					
Control Equipment: If applicable, types of air pollution control equipment (Examples: baghouse, cyclone, wet scrubber, electrostatic precipitator, thermal oxidizer, miscellaneous control device, etc.).							
Baghouse							
Please complete	e the appropriat	te air quality per	mit applicatio	n form for eac	h type of	control	

equipment that controls air emissions from this operation.

**Baghouse Application Form** 

X- Coordinate or Easting:		feet	695,119.44	meters			
Y- Coordinate or Northing:		feet	5,019,091.00	meters			
Base Elevation of Stack:	1,124	feet		meters			
Stack Height:	85.00	feet		meters			
Exit Stack Diameter	1.00	feet		meters			
Exit Stack Temperature	Ambient	degrees Fahr	enheit				
Exit Stack Velocity and/or Fl	ow Rate:	•					
Velocity:	0.33* feet per	second		meters per second			
and/or							
Flow Rate: 1,759 actual cubic feet per minute actual cubic meters per second							
*obstructed or horizontal discharge							

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



### **Air Quality Permit Application**

### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

_	Equ	ipment and Processes					
1. Unit 29: Limest	one Precrusher Building						
2.							
3.			100				
4.							
5.							
Manufacturer Information:							
Manufacturer?	TBD						
Manufacturer date?	TBD	Installation date?	Spring 2008				
Manufacturer's design	ned control efficiency?	0.01 gr/dscf	%				
Type of baghouse (pl	ease check one)?		-				
Reverse Air	X Pulse Jet	Shaker Other (s	pecify)				
Type of bags?	TBD						
Number of bags?	TBD	Air/cloth ratio? TB	D				
Baghouse Operation	n and Maintenance:						
Pressure drop across	baghouse? TBD in	iches water (minimum)	TBD inches water (maximum)				
Inlet Temperature?	Ambient Fahr	enheit (minimum) Aml	pient Fahrenheit (maximum)				
Outlet Temperature?	Ambient Fahr	enheit (minimum) Aml	pient Fahrenheit (maximum)				
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):							
Bag changing dependent on application and grain loading.							

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,119.44	meters
Y- Coordinate or Northing: 1		feet	or	5,019,091.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	85.00	feet	or		meters
Exit Stack Diameter	1.00	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fa	ahre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	0.33* feet per second	meters per second
	and/or	
Flow Rate:	1,759 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

<sup>\*</sup>obstructed or horizontal discharge



### Air Quality Permit Application Form

#### **Miscellaneous Process**

# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

4 - 44. 11 10 1 0 - 4 4 4 - 4 4 4						
1. Facility identification (i.e., Boiler #1, Unit #1, etc):	30					
2. Manufacturer: TBD	Manufactu	re date:				
3. Model number: TBD						
4. Type (i.e., steam boiler, simple cycle combustion tur	bine, generator, etc.)					
Coal Stockout System						
5. Maximum designed operating rate (name plate):						
	million Bt	us per hour heat input				
or	horsepowe	er				
or	kilowatts					
6. Check the appropriate box(es) for primary and second	dary fuels:					
Natural gas	Propane					
Distillate oil Sulfur content	Weight per	cent				
Residual oil Sulfur content	Weight per	cent				
Bituminous Coal Subbituminous	Coal Li	gnite Coal				
Coal sulfur content Weight percen	Coal ash content	Weight percent				
Other (please specify)						
7. Has a stack test been conducted (check appropriate	ox)? Yes	X No				
If a stack test has been conducted, please attach a copapplication. If the Department already has a copy of the most recent stack test.		-				
Date of most recent stack test:						
Control Equipment: If applicable, types of air pollution control equipment (Examples: baghouse, cyclone, wet scrubber, electrostatic precipitator, thermal oxidizer, miscellaneous control device, etc.).						
Baghouse						

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

information.			•			
X- Coordinate or Easting:	f	eet 6	95,016.06 meters			
Y- Coordinate or Northing:	f	eet 5,0	19,321.50 meters			
Base Elevation of Stack:	1,124 f	eet	meters			
Stack Height:	110.00 f	eet	meters			
Exit Stack Diameter	1.80 f	eet	meters			
Exit Stack Temperature	Ambient d	legrees Fahrenheit				
Exit Stack Velocity and/or Flow Rate:						
Velocity:	55.88 feet per se	econd	meters per second			
	an	d/or				
Flow Rate: 8,532.50	actual cubic feet per m	ninute	actual cubic meters per second			

Stack Information: If this application is a renewal, contact the air program. We may have this



### **Air Quality Permit Application**

### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

			Eq	uipmeı	nt and Pi	ocesse	es		
1. Unit 30: Coal S	tocko	ut System							
2.									
3.									
4.									
5.									
Manufacturer Information:									
Manufacturer?	TBI	)							
Manufacturer date?	TBI	)			Installati	on date	€?	Spring	2008
Manufacturer's design	ned co	ontrol effic	iency?	0.01	gr/dscf			%	
Type of baghouse (pl	ease (	check one)	•						
Reverse Air	X	Pulse Jet		Shake	r	Other	r (sp	ecify)	
Type of bags?		TBD	10.55C 57E K						
Number of bags?		TBD		Air/cl	oth ratio?	, ()	TBI	)	
Baghouse Operation	and	Maintena	nce:			-			
Pressure drop across	bagho	ouse? TB	D i	nches v	vater (mi	nimum	) [	TBD	inches water (maximum)
Inlet Temperature?		Ambient	Fah	renheit	(minimu	m) A	lmb	ient	Fahrenheit (maximum)
Outlet Temperature?	An	nbient	Fah	renheit	(minimu	m) A	<b>l</b> mb	ient	Fahrenheit (maximum)
Describe maintenance of baghouse (use of dye test, visual inspections, changing bag frequency, etc.):									
Bag changing dependent on application and grain loading.									
								-	

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,016.06	meters
Y- Coordinate or Northing: 1		feet	or	5,019,321.50	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	110.00	feet	or		meters
Exit Stack Diameter	1.80	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fa	hre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	55.88 feet per second	meters per second
	and/or	
Flow Rate:	8,532.50 actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.



### Air Quality Permit Application Form Miscellaneous Process

# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1 Facility identifics	tion (i.e., Boiler #1, Unit #1, etc):	33		
2. Manufacturer:	TBD	33	Manufacture	date
3. Model number:	TBD		1VIaliulaciule	date.
		1.		
	boiler, simple cycle combustion to	irbine, generato	r, etc.)	
Diesel FW Booster l	ed operating rate (name plate):			
5. Maximum design	ed operating rate (name plate):		9	
				per hour heat input
or	225.00		horsepower	
or			kilowatts	
6. Check the approp	riate box(es) for primary and seco	ondary fuels:		
Natural gas		Propan	e	
X Distillate oil	Sulfur content	0.015	Weight percen	nt
Residual oil	Sulfur content		Weight perce	nt
Bituminous C	oal Subbituminou	is Coal	Lign	ite Coal
Coal sulfur conte	ent Weight percen	nt $Coal$ ash co	ontent	Weight percent
X Other (please	specify) Biodiesel			
7. Has a stack test be	een conducted (check appropriate	box)?	Yes	X No
	peen conducted, please attach a co Department already has a copy of t st.			
Date of most recent	stack test:			
	t: If applicable, types of air polluter, electrostatic precipitator, there			

Please complete the appropriate air quality permit application form for each type of control equipment that controls air emissions from this operation.

information.	••	,	, ,	·	
X- Coordinate or Easting:		feet	6	95113.13	meters
Y- Coordinate or Northing:		feet	50	19457.00	meters
Base Elevation of Stack:	1,124	feet			meters
Stack Height:	11.00	feet			meters
Exit Stack Diameter	0.67	feet			meters
Exit Stack Temperature	749.00	degrees Fahre	enheit		
Exit Stack Velocity and/or	Flow Rate:				
Velocity:	55.76 feet per	second			meters per second
	_	and/or			
Flow Rate: 1,179.5	actual cubic feet per	minute	:	actual cubio	e meters per second

Stack Information: If this application is a renewal, contact the air program. We may have this



### Air Quality Permit Application Form Miscellaneous Process

# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler	#1, Unit #1, etc):	34		
2. Manufacturer:	TBD			Manufac	cture date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cy	cle combustion to	ırbine, gene	rator, etc.)	
Pretreatment Soda A	Ash Bin Vent				
5. Maximum design	ned operating rate	(name plate):			
				million l	Btus per hour heat input
or				horsepo	wer
or				kilowatt	s
6. Check the approp	oriate box(es) for	primary and seco	ndary fuels	:	
Natural gas		I	Pro	pane	
Distillate oil		Sulfur content		Weight p	ercent
Residual oil		Sulfur content		Weight p	ercent
Bituminous C	Coal	Subbituminou	s Coal		Lignite Coal
Coal sulfur cont	ent	Weight percer	nt   Coal as	sh content	Weight percent
Other (please	specify)				
7. Has a stack test b	een conducted (c	heck appropriate	box)?	Yes	X No
If a stack test has be application. If the I most recent stack te	Department alrea				k test report to this please specify the date of
Date of most recent	stack test:				
Control Equipment cyclone, wet scrubb				'	xamples: baghouse, s control device, etc.).
Baghouse					
Please complet	te the appropria	te air quality per	mit applic	ation form for	r each type of control

equipment that controls air emissions from this operation.

**Baghouse Application Form** 

X- Coordinate or Easting:		feet	695,191.94	meters
Y- Coordinate or Northing:		feet	5,019,029.50	meters
Base Elevation of Stack:	1,124	feet		meters
Stack Height:	60.00	feet		meters
Exit Stack Diameter	0.67	feet		meters
Exit Stack Temperature	Ambient	degrees Fahre	enheit	
Exit Stack Velocity and/or Fl	ow Rate:			
Velocity:	0.33* feet per	second		meters per second
		and/or		
Flow Rate: 600	actual cubic feet per	minute	actual cubi	c meters per second
*obstructed or horizontal disc	charge	<del> </del>		

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



### **Air Quality Permit Application**

### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

			Eq	uipme	ent and P	rocesse	S		
1. Unit 34: Pretrea	tment	t Soda Ash	Bin Ve	nt					
2.									
3.									
4.									
5.					77 (1000) (170				
Manufacturer Infor	matic	on:				<u> Paritira i manana</u> 19			enter just i 1900 gaste et aj antaŭa 190 kilonijo, di altaj utaj listori kaj graf bilitaranj
Manufacturer?	TBL	)					SERVICE DE		
Manufacturer date?	TBI	)			Installati	on date	?	Spring	2008
Manufacturer's design	ned co	ontrol effic	iency?	0.01	gr/dscf			%	
Type of baghouse (pl	ease (	check one)	?						
Reverse Air	X	Pulse Jet		Shak	er	Other	(spe	ecify)	
Type of bags?		TBD							
Number of bags?	Ī	TBD		Air/c	loth ratio	,	ГBD	)	
Baghouse Operation	ı and	Maintena	nce:						
Pressure drop across	bagho	ouse? TE	D i	nches	water (mi	nimum)	) []	ΓBD	inches water (maximum)
Inlet Temperature?		Ambient	Fah	renhei	t (minimu	m) A	mbi	ent	Fahrenheit (maximum)
Outlet Temperature?	An	nbient	Fah	renhei	t (minimu	m) Ā	mbi	ent	Fahrenheit (maximum)
Describe maintenance	e of b	aghouse (u	se of dy	ye test,	, visual in	spection	ns, c	hangin	g bag frequency, etc.):
Bag changing depend	lent o	n application	on and	grain l	oading.				
				1000 5400					
							115000 QBB/1		

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,191.94	meters
Y- Coordinate or Northing: 1		feet	or	5,019,029.50	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	60.00	feet	or		meters
Exit Stack Diameter	0.67	feet	or		meters
Exit Stack Temperature	Ambient	degrees Fa	hre	nheit	

Exit Stack Velocity and/or Flow Rate:

Velocity:	0.33* feet per second	meters per second
	and/or	
Flow Rate:	actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

<sup>\*</sup>obstructed or horizontal discharge



### Air Quality Permit Application Form Miscellaneous Process

# This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit or Minor Operating Permit. (please complete shaded areas)

1. Facility identifica	ation (i.e., Boiler #1,	Unit #1, etc):	35		
2. Manufacturer:	TBD			Manufacture	date:
3. Model number:	TBD				
4. Type (i.e., steam	boiler, simple cycle	combustion to	ırbine, generato	r, etc.)	
Pretreatment Lime	Bin Vent				
5. Maximum design	ned operating rate (na	ame plate):			
				million Btus p	per hour heat input
or				horsepower	
or				kilowatts	
6. Check the approp	oriate box(es) for pri	mary and seco	ondary fuels:	_	
Natural gas			Propan	e	
Distillate oil	S	ulfur content		Weight percen	t
Residual oil	S	ulfur content		Weight percen	t
Bituminous C	Coal	Subbituminou	is Coal	Ligni	te Coal
Coal sulfur conte	ent	Weight percer	nt   Coal ash co	ontent	Weight percent
Other (please	specify)				
7. Has a stack test b	een conducted (chec	k appropriate	box)?	Yes	X No
					report to this e specify the date of
Date of most recent	stack test:				
<del>-</del> -	at: If applicable, type er, electrostatic prec	-	_		
Baghouse					
Please complet	e the appropriate a	ir anality ner	rmit annlication	n form for each	type of control

equipment that controls air emissions from this operation.

X- Coordinate or Easting:		feet	695,185.94	meters
Y- Coordinate or Northing:		feet	5,019,028.00	meters
Base Elevation of Stack:	1,124	feet		meters
Stack Height:	60.00	feet		meters
Exit Stack Diameter	0.67	feet		meters
Exit Stack Temperature	Ambient	degrees Fahre	enheit	
Exit Stack Velocity and/or Flo	ow Rate:			
Velocity:	0.33* feet per	second		meters per second
	8	and/or		
Flow Rate: 600	actual cubic feet per	minute	actual cubi	c meters per second
*obstructed or horizontal disc	harge	<u></u>	<u> </u>	

Stack Information: If this application is a renewal, contact the air program. We may have this

information.



### **Air Quality Permit Application**

### **Baghouse**

This form is to be submitted, if necessary, along with the Title V (Part 70) Operating Permit, Minor Operating Permit, or the General Permits.

(please complete shaded areas)

Equipment and processes served by this baghouse (please list all equipment and processes):

			Equip	ment a	nd Pr	ocesses			
1. Unit 35: Pretreat	tment	Lime Bin V	<sup>7</sup> ent						
2.									
3.									
4.									
5.									
Manufacturer Infor	matic	on:							
Manufacturer?	TBI	)							
Manufacturer date?	TBI	)		Ins	tallatio	n date?	Spring	2008	
Manufacturer's design	red co	ontrol efficie	ency? 0.	01 gr/	dscf		%		
Type of baghouse (ple	ease (	check one)?					•		
Reverse Air	$\mathbf{X}$	Pulse Jet	Sh	aker		Other (sp	ecify)		
Type of bags?		TBD							
Number of bags?		TBD	Ai	r/cloth	ratio?	TB	D		
Baghouse Operation	and	Maintenan	ce:						
Pressure drop across l	oagho	ouse? TBI	inch	es wate	er (min	imum)	TBD	inches water (ma	ximum)
Inlet Temperature?		Ambient	Fahrenl	eit (m	inimur	n) Amb	oient	Fahrenheit (maxi	imum)
Outlet Temperature?	An	bient	Fahrenl	eit (m	inimur	n) Amb	ient	Fahrenheit (maxi	imum)
Describe maintenance	of b	aghouse (us	e of dye te	st, vis	ual ins	pections,	changin	g bag frequency, e	tc.):
Bag changing depend	ent o	n application	ı and grai	n loadi	ng.				

Stack Information: If this application is a renewal, contact the air program. We may have this information.

X- Coordinate or Easting: 1		feet	or	695,185.94	meters
Y- Coordinate or Northing: 1		feet	or	5,019,028.00	meters
Base Elevation of Stack: 1	1,124	feet	or		meters
Stack Height:	60.00	feet	or		meters
Exit Stack Diameter	0.67	feet	or		meters
Exit Stack Temperature	Ambient	degrees I	ahre	enheit	•

Exit Stack Velocity and/or Flow Rate:

Velocity:	0.33* feet per second	meters per second
	and/or	
Flow Rate:	actual cubic feet per minute	actual cubic meters per second

<sup>&</sup>lt;sup>1</sup> - Portable asphalt plants, rock crushers, or concrete plants do not have to provide the requested information in these categories.

<sup>\*</sup>obstructed or horizontal discharge

EMISSIONS POINT TABLE

FORT D, BM, NOTE 6)

SYSTEM DESIGNATION

INCOME DESIGNATION

IN EMISSIONS POINT TABLE THE DIMPING IS PROVIDED FOR ARE PERMITTING PURPOSES ONLY AND IS NOT CONSIDERED A DRAWING REQUIRED FOR CONSTRUCTION. TICODINI COORDINATES ARE QUIEN IN BUP II PLANT COORDINATE SYSTEM, FOR CONVERSION TO OTHER SYSTEMS SEE CONVERSION TABLE THIS DRIVEND, E....3 LEGEND .... COORDINATE CONVERSIONS O 16,000 5,000 2,866,396,8962 2,866,002,2601 685,266,3008 680,300,3630 **જે** يصر ø NOT TO BE USED FOR CONSTRUCTION | D | OB/16/06 | GOR/DN, RGYSIONS | G. OB/07/06 | SRYSIQ CON, YARD ARCA | G. OB/07/06 | SRYSIQ CON, YARD ARCA | G. OB/07/06 | SRYSIQ CON, CANDER, REVOUL | G. OB/16/06 | SRYSIQ CON, CANDER, REVOUL | G. OB/16/06 | SRYSIQ CON, CANDER, REVOUL | G. OB/16/06 | G. OB/16/06 | SRYSIQ CON, CANDER, CANDE BLACK & VEATCH

CORPORATION

STEEL S G 01/11/07 GDEPM, #0/13/04 F 10/08/06 REDUCED SCOPE RED E D0/11/04 COOLBE TORTE RED BIG STONE II CO-OWNERS 142662-CSTA-S1020 G SITE EMISSIONS POINTS

EXISTING BIG STONE I POWER PLANT LEGEND BIG STONE II POWER PLANT LEGEND FACILITY FACILITY NORTH EAST COMMUNION BURDON
FRANCE PRITER

DE PINAS (GORE D)
FOOD BOOSTICE PRINS (GORE D)
FOR GORE BURDON (GORE D)
FOR GORE BURDON (GORE D)
FOOD BURDON ( COORDINATE CONVERSIONS 20,000 10,000 505,436,2867 595,430,8247 5,019,710,8672 6,016,498,2438 15,000 B,000 2,862,362,6652 2,868,002,2801 685,268,3608 685,300,3630 9 (....) 0 **O** (6) ⊗ 9 0 **9 6** 70 3000000 080 **8** (3) 10 NOT TO BE USED FOR CONSTRUCTION BLACK & VEATCH

SO ONE SO IN.

SO IN. W BIG STONE II CO-OWNERS 142662-CSTA-S1001 SITE ARRANGEMENT MAIN PLANT AREA

\_

_
ੜ
₫.
≓.
ឆ
፷
š.
Ö
⊆
×
₽
퓲
ä
₹.
'n
Ë
유
ŏ
ᅲ
오
ਰ
ā
₹
≓
Ø
ō
으
Ω.
뿄
₫
_
₩
≊.
Š
vision
vision (
vision (Ju
vision (Jun
vision (June
vision (June 20
vision (June 200
vision (June 2006)
vision (June 2006) a
vision (June 2006) an
vision (June 2006) and
vision (June 2006) and or
vision (June 2006) and orig
vision (June 2006) and origin
vision (June 2006) and original
vision (June 2006) and original a
vision (June 2006) and original app
and original app
vision (June 2006) and original applica
and original app
and original application (Jui
and original application (Jui
and original application (Jui
and original app

	0.2 lb/1000 gal	5 lb/1000 gal	1[lb/1000 gal	3 1961 Bros steam heating boiler No. 2 FO	
	0.2 lb/1000 gal	5 lb/1000 gal	1 lb/1000 gal	2 1973 combustion steam boiler No. 2 FO	
	VOC	ĈO	PM	STACKID Name	STA
			1,020 MMBtu/MMcf	Natural gas heating value	
			0.05 % Sulfur	Old Units Fuel Oil - % Sulfur	
			140,000 Btu/gal	Heating Value - Liquid Fuels - Distillate Oil	
		-		ı	ſ
assumed half of NMHC+NOX factor was NMHC	1,50 g/bhp-hr	2.60 g/bhp-hr	0.15 g/bhp-hr	33   Diesel FW Booster Pump (Coal Area)	ω
	0.36 lb/MMBtu	0.95 lb/MMBtu	0.31   lb/MMBtu	31EFP Existing Fire Pump	31E
assumed half of NMHC+NOX factor was NMHC	1.50 g/bhp-hr	2.60 g/bhp-hr	0.15 g/bhp-hr	25 Diesel FW Booster Pump (Boiler)	22
assumed half of NMHC+NOX factor was NMHC	2.40 g/bhp-hr	2.60 g/bhp-hr	0.15 g/bhp-hr	15 Emergency Diesel Generator - BSP II	==
assumed half of NMHC+NOX factor was NMHC	1.50 g/bhp-hr	2.60 g/bhp-hr	0.15 g/bhp-hr	14 Emergency Fire Water Pump - BSP II	۲
	0.0036 lb/MMBtu	0.15 lb/MMBtu	0.03 lb/MMBtu	13 Chimney - BSP II	-
	7.05E-04 lb/hp-hr	5.50E-03 lb/hp-hr	0.0007 lb/hp-hr	4 1974 WPS emergency generator No. 2 FO	
hardcoded to 0.01 instead of calculated 0.007	1.43E-03 lb/MMBtu	0.04 lb/MMBtu	0.01 lb/MMBtu	3 1961 Bros steam heating boiler No. 2 FO	[
hardcoded to 0.01 instead of calculated 0.007	1.43E-03 lb/MMBtu	0.04 lib/MMBtu	0.01 lb/MM8tu	2 1973 combustion steam boiler No. 2 FO	
filterable only	0.0064 lb/MMBtu	0.079  Ib/MMBtu	0.26 lb/MMBtu	1 B & W steam generator (old)	<u> </u>
	VOC	00	PM10	STACKID Name	STA
		Emission Factors			

CTACKE	Nemo	<u></u>	Emissions (lb/hr)			Emissions (tpy)		Hours of
0170110	Name	PM10	00	Voc	PM10	00	Voc	Operation
-1	B & W steam generator (old)	1,508.00	458.20	37.12	6,605.04	2,006.92	162.59	8760
2	1973 combustion steam boiler No. 2 FO	2.10	7.50	0.30	9.20	32.85	1.31	8760
3	1961 Bros steam heating boiler No. 2 FO	0.98	3.50	0.14	4.29	15.33	0.61	8760
4	1974 WPS emergency generator No. 2 FO	0.94	7.38	0.95	4.11	32.31	4.14	8760
13	Chimney - BSP II	180.00	900,000	21.60	788.40	3,942.00	94.61	8760
14	Emergency Fire Water Pump - BSP II	0.14	2.41	1.39	0.03	0.60	0.35	500
15	Emergency Diesel Generator - BSP II	0.73	12.73	11.75	0.18	3,18	2.94	500
25	Diesel FW Booster Pump (Boiler)	0.07	1.29	0.74	0.02	0.32	0.19	500
31EFP	Existing Fire Pump	1.00	3.08	1.17	0.25	0.77	0.29	500
33	Diesel FW Booster Pump (Coal Area)	0.07	1.29	0.74	0.02	0.32	0.19	500

<		HP	225 HP	Diesel FW Booster Pump (Coal Area)	33
<	2,500.00	mmBtu/hr	3.24	Existing Fire Pump	31EFP
<	1179.5	HP	225.00	Diesel FW Booster Pump (Boiler)	25
<	10,650.00	HP	2,220.00	Emergency Diesel Generator - BSP II	15
<	2486.2	HP	420.00	Emergency Fire Water Pump - BSP II	14
<		mmBtu/hr	6,000.00	Chimney - BSP II	13
U	2,860	푸	1341.022 HP	1974 WPS emergency generator No. 2 FO	4
<	19,620	98 mmBtu/hr	98	1961 Bros steam heating boiler No. 2 FO	3
<	42,047	210 mmBtu/hr	210	1973 combustion steam boiler No. 2 FO	2
<	1,323,845	5800 mmBtu/hr	5800	B & W steam generator (old)	1
Type*	ACFM	Size Units	Size		STACKID
Discharge					



					_								
		•				Control % or	Factor	Factor			PM10	PM2.5	1
Stack ID	Description	passive, non vertical?	acfm	dscfm	hr	Natural Limits	(PM10)	(PM2.5)	Units	PM10 (lb/hr)	(ton/yr)	(lb/hr)	PM2.5 (ton/yr)
7a_d_hr	Rotary car dumper building	not passive, vertical	122,000	147,690	5000	18 hours/day	0.010	0.010	gr/dscf	9.49	31.65	9.49	31.65
- 8	Fuel transfer house	not passive, vertical	15,650	18,945	8760		0.020	0.020	gr/dscf	3.25	14.23	3.25	14.23
9	North fuel conveying systems	not passive, non vertical	14,200	14,440	8760		0.01	0.010	gr/dscf	1.24	5,42	1,24	5,42
10	South fuel conveying systems	not passive, non vertical	16,500	16,779	8760		0.01	0.010	gr/dscf	1.44	6.30	1.44	6.30
17	Coal Reclaim System	passive, vertical	6,750	8,171	8760		10.0	0.010	gr/dscf	0.58	2.53	0.58	2.53
22	Coal Tripper/Silo Fill System	passive, vertical	35,500	36,099	8760		0.01	0.010	gr/dscf	3.04	13.33	3.04	I3.33
26	Coal Plant Transfer System	passive, vertical	4,500	5,448	8760		0.01	0.010	gr/dscf	0.39	1.69	0.39	1.69
27	Coal Crusher Building - BSP	passive, vertical	15,000	18,159	8760		0.01	0.010	gr/dscf	1.29	5.63	1.29	5.63
30	Coal Stockout	passive, vertical	8532.5	10,329	5000	18 hours/day	0.01	0.010	gr/dscf	0.66	2.21	0.66	2.21
IAC_WE	Inactive Coal Pile Wind Erosi	ол			8760	25%				0.53	2,33	0.08	0,35
IAC_PM	Inactive Coal Pile Maintenand	æ			8760	50%	1.34	0.13	lb/VMT	0.60	1.91	0.06	0.19
IAC_LI	Inactive Coal Pile Load-in	3600.0	tons/hr			25%	0.000114	0.000017	lb/ton	0.31	0.03	0.05	4.52E-03

### Fly Ash Handling System Emission Points

Γ				_			Factor	Factor			PM10	PM2.5	PM2.5
L	Stack ID	Description	passive, non vertical?	acfm	dscfm	<u>hr</u>	(PM10)	(PM2.5)	Units	PM10 (lb/hr)	(ton/yr)	(lb/hr)	(ton/yr)
	- 11	Fly ash storage silo	not passive, non vertical	3,520.00	4,261	8760	0.01	0.01	gr/dscf	0.37	1.60	0.37	1.60
	23ab	Fly ash silo bin vent	not passive, vertical	9,000.00	10,895	8760	10,0	0,01	gr/dscf	0.93	4.09	0,93	4,09
Е	34	Pretreatment Soda Ash Bin V	not passive, non vertical	600	726	8760	0.01	0.01	gr/dscf	0.06	0.27	0.06	0.27
Γ	35	Pretreatment Lime Bin Vent	not passive, non vertical	600	726	8760	0,01	10,0	gr/dscf	0.06	0.27	0,06	0,27

### Limestone Handling System Emission Points

	1					Factor	Factor			PM10	PM2.5	PM2.5
Stack ID	Description	passive, non vertical?	acfm	dscfm	hr	(PM10)	(PM2.5)	Units	PM10 (lb/hr)	(ton/yr)	(lb/hr)	(ton/yr)
12	Lime storage silo	not passive, non vertical	1,239.08	1,500.00	8760	0.01	0.01	gr/dscf	0.13	0.56	0.13	0.56
20	Limestone Reclaim System	passive, vertical	6,000,00	7,263,43	8760	0.01	0.01	gr/dscf	0.62	2.73	0.62	2.73
21	Limestone Receiving System	passive, vertical	5,000,00	6,052.86	8760	0.01	0.01	gr/dscf	0.52	2.27	0.52	2.27
24	Limestone Day Bins Vent	not passive, non vertical	3,281.00	3,971,88	8760	0.01	0.01	gr/dscf	0.34	1.49	0.34	1.49
29	Limestone Precrusher Buildin	not passive, non vertical	1,759.00	2,129,39	8760	10.0	0.01	gr/dscf	0.18	0.80	0.18	0.80
28	Limestone stackout conveyor	11.00	tph		8760	3,32E-04	5.02E-05	lb/ton	0.0036	0.02	0.001	0.00
LS_WE	Limestone Pile Wind Erosion	(cover)			8760				0.04	0.17	0.01	0.03

### Gypsum Handling System Emission Points

				Factor	Factor					PM2.5
Stack ID	Description	Thruput	Units	(lb PM10/ton)	(lb PM2.5/ton)	hr	PM10 (lb/hr)	PM10 (ton/yr)	PM2.5 (lb/hr)	(ton/yr)
GP_WE	Gypsum Pile Wind Erosion					8760	0.01	0.04	0.001	0.00628
GP_LI	Gypsum Pile Load-in	100	tons/hr	0.0003	5.02E-05	8760	0.03	0.15	0.01	0.02200
GP_LO	Gypsum Pile Load-out	82.5	tons/hr	0.0003	5.02E-05	8760	0.03	0.12	0.00414	0.01815

#### Landfill System

Emission Points

				Factor	Factor						PM2.5
Stack ID	Description	Thruput	Units	(lb PM10/ton)	(lb PM2.5/ton)	Control %	hr	PM10 (lb/hr)	PM10 (ton/yr)	PM2.5 (lb/hr)	(ton/yr)
LF_WE	Landfill Wind Erosion						8760	0.66	2.87	0.10	0.43
LF_LI	Landfill Load-in	150.00	tph	0.0003	5.02E-05	50%	8760	0.02	0,11	0.0038	0.02
LF_PM	Landfill Pile Maintenance	0.56	VMT/hr	0.96	0.10	50%	8760	0,27	0,86	0.03	0.09



 $E = \frac{k (0.0032) (U/5)^{1.3}}{(M/2)^{1.4}}$ 

(M/2)***				_					
	pm10	pm2.5							
- "						New baghouses			
k =	0.35	0.053				(grain loading)	0.01	gr/dscf	Skidmore
U = mean wind speed (mph)	11.10								
M = material moisture content		<u> </u>		Coal		Limestone	Gypsum		Ash
	coal	21.42		% moisture (for piles)	21.42	Density (lb/ft3)	00.01	moisture	Moisture %
	ash	1,00		density (lb/ft3)	45	85	65.00	lb/cf density	for dry loadout
	gypsum			coal pile load in tph	3,600.00	Moisture %	100	load in tph	1,00
	landfill	10,00				10.00	82.5	load out tph	
E (lb PM10/ton)	Limestone	10.00						-	
	coal	1.14E-04	1.73E-05						
	ash	8.33E-03	1.26E-03						
	gypsum	3.32E-04	5.02E-05						

Limestone Wind Erosion - See related spreadsheets: From AP-42, Section 13.2.5 (1/95)

landfill

		Height	Density	Amount	Area	Moisture	Angle of	Threshold	PM10	PM10	PM2.5	PM2.5
		A	Ib/ft3	tons	ft2	%	Slope	Friction	lb/hr	tpy	lb/hr	tpy
LS_WE	Limestone Pile Wind Erosion	53.00	85,00	15,000	20,106	10.00	26.6	0.62	0.04	0.17	0.01	0.03
IAC_WE	Inactive Coal Pile Wind Erosi	45.00	_ 45.00	697,000	566,280.00	21,42	26.6	1.02	0.71	3.11	0,11	0.47
GP WE	Gypsum Pile Wind Erosion	25,00	65.00	9,572	5,000	10.00	26.6	0.62	0.01	0.04	0.00	0.01
LF_WE	Landfill Wind Erosion	15.00	65,00	1,300,000	522,720	10.00	26.6	1.02	0.66	2.87	0.10	0.43

#### Pile Maintenance - Unpaved Haul Road Emissions: From AP-42, Section 13.2.2 (2/03)

Emission Factor =>

 $E_{hourly} = k(s/12)^a (W/3)^b$  $E_{\text{max}} = k(s/12)^a (W/3)^h*((365-P)/365)$ 

3.32E-04

3.32E-04

Vehicle Miles Traveled (VMT) = 2 \* Length of Segment \* Maximum Hourly Amount Pushed

Weight of Vehicle

		Cannos - K(5/12) a (44/5) U	((303°F)/303)			¥¢
				_		
	Where:	E = Emission factor (pound	is per VMT)			
		PM10	PM2.5			
	k = constant (PM10)	1.5	0.	15	Taken from Table 13.2.2-2 in AP-42	
	a = constant	0.9		0.9	Taken from Table 13.2.2-2 in AP-42	
	b = constant	0.45		45	Taken from Table 13.2.2-2 in AP-42	
s = sı	rface material silt content (%)	2.2			AP-42 table 13.2.4-1, 1/95, coal fired power plant coal as received	
p = Number of d	ays with 0.01" of precipitation	100	Į:	00		
Maximum hou	rly amount pushed -scraper =	412.50	tons		Inactive Coal Pile	
Maximum hourly ar	nount pushed -wheel loader =	122.85	tons		Landfill	
	Capacity of dozer=	25	tons		Inactive Coal Pile	
	maximum speed (estimate)	2.50	mph			
	7	0.00	:loo	7	Institute Carl Bile and Landfill Distances	

5.02E-05

5.02E-05

					Uncontrolled							
		# sources	W		PM10 hourly	PM10	PM10 annual	PM10	PM2.5 hourly	PM2.5	PM2.5 annua	PM2,5
			tons	VMT/hr	lb/VMT	lb/hr	lb/VMT	tpy	Ib/VMT	lb/hr	lb/VMT	tpy
IAC PM	Inactive Coal Pile Mainten	36.00	70.00	0.89	1.34	1.20	0.98	3,82	0.13	0.12		0.38
LF_PM	Landfill Pile Maintenance	23.00	33,00	0.56	0.96	0.54	0.70	1.72	0.10	0.05	0.07	0.17

#### **Haul Road Emission Calculations**

Paved Haul Road Emission Equations, From AP-42 Section 13.2.1 (12/03)

Emission Factor => E =  $[k * (sL/2)^0.65 * (W/3)^1.5 - C] * (1-(P/4N)) =$ 

Where:

Control for watering of paved roads per BACM 50%

E = Emission factor (pounds per VMT)

C = emission factor for brake /tire wear 0.00047

k = constant (PM10) 0.016 Taken from Table 13.2.1-1 in AP-42

k = constant (PM2.5) 0.0024 Taken from Table 13.2.1-1 in AP-42
Table 13.2.1-3, ubiquitous baseline

sL = Silt loading (g/m2) 0.6 for <500 trucks per day

W = mean vehicle weight (tons) Varies by truck type

P = Number of days with 0.01" of precipitation
N = number of days in averaging period
100 Figure 13.2.1-2
365 365 days per year

			Weight	NH	NH		NAAQS	Increment
	Truck	Loaded	Unloaded	PM10	PM2.5	NAAQS Hourly	Annual	Hourly
Description	Туре	tons	tons	lb /VMT	lb/VMT	trips/hr	trips/hr	trips/hr
Tires	Truck	40	15	0.0943	0.0140	1.00	1.00	-
Limestone	Truck	40	15	0.0943	0.0140	3.00	1.15	2.0000
Bottom Ash Unit 1	Truck	40	15	0.0943	0.0140	2.00	1.58	-
Bottom Ash Unit 2	Truck	40	15	0.0943	0.0140	1.00	0.50	1.0000
Fly Ash Unit 1	Truck	40	15	0.0943	0.0140	1.00	0.84	-
Fly Ash Unit 2	Truck	40	15	0.0943	0.0140	3.00	2.01	3.0000
Gypsum	Truck	40	15	0.0943	0.0140	5.00	2.47	3.0000
Landfill	Articulated truck	76	36	0.2746	0.0410	11.00	7.40	4.5000

	Loaded	Unloaded	Load
	tons	tons	tons
Truck	40	15	25
Scraper	89	51	38
Articulated truck	76	36	40

	naaqs	naaqs	increment	increment
	trucks per day	trucks per year	trucks per day	trucks per year
Tires	1	8,760	-	
Limestone	3	10,100	2	10,100
Bottom Ash Unit 1	2	13,800	-	
Bottom Ash Unit 2	1	4,400	1	4,400
Fly Ash Unit 1	1	7,400	_	
Fly Ash Unit 2	3	17,600	3	17,600
Gypsum	5	21,600	3	21,600
Landfill	11	64.800	9	43,600

	# volume sources	27	9	20	5	11	9	6	4	5	59	8	52
Increment Annual	length (m)	475.86	145.61	347.46	73.15	180.94	134.77	81,44	54.86	68.52	1,055.76	119.87	918.63
trips/hr	ID	A	В	С	D	E	F	Н	I	J	L	M	T
		0	0	2	0	0	1	0	0	0	0	0	2
1.1530		2	1	2	1	1	0	0	0	0	0	0	0
		2	1	2	1	1	0	0	0	0	0	0	0
0.5023		2	1	2	_1	1	0	0_	1	1	0	0	0
		2	1	2	1	1	0	1	0	1	0	0	0
2.0091		2	1	2	1	1	0	0_	1	1	0	0	0
2.4658		2	0	2	0	2	0	0	0	0	0	1	0
4.9772		0	0	0	0	0	0	0	0	0	2	0	0
PM10	PM10 lb /VMT	1.13	0.47	1.32	0.47	0.66	0.09	0.09	0.19	0.28	0.55	0.09	0.19
PM2.5	PM2.5 lb/VMT	0.17	0.07	0.20	0.07	0.10	0.01	0.01	0.03	0.04	0.08	0.01	0.03
naaqs													
hourly	VMT/hr	8.87	0.90	6.91	0.45	2.25	0.08	0.05	0.14	0.21	14.43	0.37	1.14
nh10	PM10 lb /segment	3.10E-02	9.48E-03	3.26E-02	8.58E-03	1.93E-02	8.78E-04	7.96E-04	3.22E-03	4.02E-03	6.72E-02	4.39E-03	2.07E-03
nh25	PM2.5 lb/segment	4.59E-03	1.40E-03	4.82E-03	1.27E-03	2.85E-03	1.30E-04	1.18E-04	4.76E-04	5.95E-04	1.00E-02	6.50E-04	3.07E-04
naaqs													
annual	VMT/hr	5.06	0.55	4.12	0.28	1.24	0.08	0.04	0.09	0.14	9.71	0.18	1.14
na25	PM2.5 lb/segment	2.62E-03	8.54E-04	2.88E-03	7.72E-04	1.57E-03	1.30E-04	9.95E-05	2.99E-04	3.99E-04	6.74E-03	3.21E-04	3.07E-04
Increment													
hourly	VMT/hr	5.32	0.54	3.89	0.27	1.35	-	-	0.14	0.17	5.90	0.22	
ih10	PM10 lb /segment	1.86E-02	5.69E-03	1.83E-02	5.15E-03	1.16E-02	0.00E+00	0.00E+00	3.22E-03	3.21E-03	2.75E-02	2.64E-03	0.00E+00
increment											S. Carlons		
annual	VMT/hr	0.21	0.02	0.15	0.01	0.06			0.01	0.01	0.36	0.01	
ia10	PM10 lb /segment	7.19E-04	2.15E-04	7.19E-04	2.15E-04	5.04E-04	0.00E+00	0.00E+00	1.47E-04	1.47E-04	1.70E-03	1.45E-04	0.00E+00

$$u_s^+ = u_{10}^+ - \frac{u_s}{u_r}$$

For this pile, use Pile B1 from Figure 13.2.5-2

Table 13.2.5-3 - Subarea Distribution for regimes of us/ur

Active	Surface Area		Pile Subarea	% of Pile Surface		
	20,106.19 ft2		0.2a	5	Are	
	1,867.93	m2	0.2b	2	0.2	672.45
			0.2c	29	0.6	933.96
			0.6a	26	0.9	261.51
			0.6b	24		
			0.9	14		

http://www5.ncdc.noaa.gov/documentlibrary/pdf/wind1996.pdf

Threshold Friction Velocity = 0.62

	TILLD.//WWW.J.TICUC.	ivaa.gov/docuii	iendibrai y/pul/wi	ma rado,par											
	J	an	Feb	Mar	Apr	May	Jun	Jul	Αι	ug S	iep O	ct No	v D	ec	Ann
Huron	DIR N	1M	NW	NNW	NNW	NW	NW	N	N	S	SE S	SE SS	E S	SE	SSE
	SPD	12	11	13	1	3	13	11	11	11	11	11	12	11	12
mph	PGU	56	62	55	6	4	60	63	82	76	54	52	58	60	82
m/sec	PGU	25.20	27.90	24.75	28.80	27.00	28	.35	36.90	34.20	24.30	23.40	26.10	27.00	36.90

Annual Peak Gust Analysis
Wind Speed 0.2 0.6 0.9
36.90 0.74 2.21 3.32

			PM10	PM2.5
u* - ut* (m/s)	P (g/m^2/yr)	Area (m^2)	E (g/yr)	E (g/yr)
0.12	3.76	672.45	1,263.40	189.51
1.59	187.22	933.96	87,427.59	13,114.14
2 70	490.66	261 51	64 155 95	9 623 39

152,846.94 22,927.04 g/yr 336.96 50.54 lb/yr 0.17 0.03 tpy

$$u_s^+ = u_{10}^+ \frac{u_s}{u_r}$$

For this pile, use Pile B1 from Figure 13.2.5-2

Table 13.2.5-3 - Subarea Distribution for regimes of us/ur

Active	Surface Area	Pile Subarea	% of Pile Surface		
	566,280.00 ft2	0.2a	5	,	Area
	52,609.13 m2	0.2b	2	0.2	18939.29
		0.2c	29	0.6	26304.57
		0.6a	26	0.9	7365.28
		0.6b	24		
		0.9	14		
	Threshold Friction Veloci	ity = 1.02			

http://www5.ncdc.noaa.gov/documentlibrary/pdf/wind1996.pdf

	Into an interest	noda.go naooc	miletimbren frpen	Willia 1000,pul											
	J	lan	Feb	Mar	Apr	May	Jun	Ju	ıl A	lug S	Sep C	Oct No	ov De	ec Ai	nn
Huron	DIR N	1W	NW	NNW	NNW	NW	NW	N	N	1 5	SSE S	SSE SS	SE SS	SE S	SE
	SPD	13	2 1	1	13	13	13	11	11	11	11	11	12	11	12
mph	PGU	58	5 6	2	55	64	60	63	82	76	54	52	58	60	82
m/sec	PGU	25.20	27.90	24.75	28.	.80 2	27.00	28.35	36.90	34.20	24.30	23.40	26.10	27.00	36.90

Annual Peak Gust Analysis 0.6 Wind Speed 0.2 0.9 36.90 0.74 2.21 3.32 PM2.5 u\* - ut\* (m/s) P (g/m^2/yr) Area (m^2) E (g/yr) E (g/yr) 0.00 0.00 18939.29 0.00 1.19 112.54 26304.57 1480117.04 222,017.56 2.30 364.61 7365.28 1342733.97 201,410.10 2822851.01 423,427.65 g/yr 933.48 lb/yr 6223.22 3.11 0.47 tpy

$$u_s^+ = u_{10}^+ \frac{u_s}{u_r}$$

For this pile, use Pile B1 from Figure 13.2.5-2

Table 13.2.5-3 - Subarea Distribution for regimes of us/ur

Active	Surface Area	Pile Subarea	% of Pile Surface		
	5,000.00 ft2	0.2a	5	-	rea
	464.52 m2	0.2b	2	0.2	167.23
		0.2c	29	0.6	232.26
		0.6a	26	0.9	65.03
		0.6b	24		
		0.9	14		
	Threshold Friction Veloc	ity = 0.62			

http://www5.ncdc.noaa.gov/documentlibrary/pdf/wind1996.pdf

	THE STATE OF THE S	ioua.gov/aoouiii	Citabiai jipan mila	1000.041										
	J	an I	Feb M	ar Apr	May	Jun	Jul	Aug	g Ser	Oct	Nov	Dec	Ann	
Huron	DIR N	1W I	IN W	NW NNV	/ NW	NW	N	N	SS	E SSE	SSE	SSE	SSE	
	SPD	12	11	13	13	13	11	11	11	11	11	12	11	12
mph	PGU	56	62	55	64	60	63	82	76	54	52	58	60	82
m/sec	PGU	25.20	27.90	24.75	28.80 2	27.00	28.35	36.90	34.20	24.30	23.40	26.10 2	7.00 3	86.90

**Annual Peak Gust Analysis** Wind Speed 0.2 0.6 0.9 36.90 0.74 2.21 3.32 PM2.5 u\* - ut\* (m/s) P (g/m^2/yr) Area (m^2) E (g/yr) E (g/yr) 0.12 3.76 167.23 314.18 47.13 1.59 187.22 232.26 21741.46 3,261.22 2.70 490.66 65.03 15954.28 2,393.14 38009.92 5,701.49 g/yr 12.57 lb/yr 83.80 0.04 0.01 tpy

$$u_s^+ = u_{10}^+ - \frac{u_s}{u_r}$$

For this pile, use Pile B1 from Figure 13.2.5-2

Table 13.2.5-3 - Subarea Distribution for regimes of us/ur

Active	Surface Area	Pile Subarea	% of Pile Surface		
	522,720.00 ft2	0.2a	5		Area
	48,562.28 m2	0.2b	2	0.2	17482.42
		0.2c	29	0.6	24281.14
		0.6a	26	0.9	6798.72
		0.6b	24		
		0.9	14		
		WHITE THE PARTY OF			
	Threshold Friction Velocity =	1.02			

http://www5.ncdc.noaa.gov/documentlibrary/pdf/wind1996.pdf

	TREP.IT TETT TO TO TO CO.	noda.go vraoce	attroritation di Trp di	Willia 1000.pai											
	J	lan	Feb	Mar	Apr	May	/ Jui	n Ju	ıl /	Aug	Sep	Oct	Nov	Dec A	nn
Huron	DIR N	1W	NW	NNW	NNW	NW	NV	V N		N	SSE	SSE	SSE	SSE S	SSE
	SPD	1:	2	11	13	13	13	11	11	11	11	11	12	11	12
mph	PGU	50	6	62	55	64	60	63	82	76	54	52	58	60	82
m/sec	PGU	25.20	27.90	24.75	28	.80	27.00	28.35	36.90	34.20	24.30	23.40	26.10	27.00	36.90

Wind Speed	0.2	0.6	0.9		
36.90	0.74	2.21	3.32		
				PM2.5	
u* - ut* (m/s)	P (g/m <sup>2</sup> /yr)	Area (m^2)	E (g/yr)	E (g/yr)	
0.00	0.00	17482.42	0.00		
1.19	112.54	24281.14	1366261.88	204,939.28	
2.30	364.61	6798.72	1239446.74	185,917.01	
			2605708.63	390,856.29	g/yr
			5744.51	861.68	lb/yr
			2.87	0.43	tpy

#### **Cooling Tower**

Tower Circulation Rate = 312,540 gallons per minute

Tower Drift Efficiency = 0.0005%

Water loss due to drift (tower total) = 1.56 gallons per minute

Total Dissolved Solids = 6,000.00 ppm

Water density = 8.34 pounds per gallon

Pounds of water lost due to drift = 13.03 pounds per minute

0.006 pounds solids per pound water

0.078 pounds particulate per minute

4.69 pounds per hour - entire tower

0.250 lb/MMGal cooled

Cells = 18

Emission Point	lb/hr/cell	
NewCell1	0.26065836	1
NewCell2	0.26065836	2
NewCell3	0.26065836	3
NewCell4	0.26065836	4
NewCell5	0.26065836	5
NewCell6	0.26065836	6
NewCell7	0.26065836	7
NewCell8	0.26065836	8
NewCell9	0.26065836	9
NewCell10	0.26065836	10
NewCell11	0.26065836	11
NewCell12	0.26065836	12
NewCell13	0.26065836	13
NewCell14	0.26065836	14
NewCell15	0.26065836	15
NewCell16	0.26065836	16
NewCell17	0.26065836	17
NewCell18	0.26065836	18

Cooling Tower (Label = O)		
18	cells	
Tower Circulation Rate	312,540.00	gpm
Tower Drift Efficiency	0.00050%	%
Total Dissolved Solids	6,000.00	ppm
Exhaust Flow From Each Cell	2,032,189	acfm
Exhaust Temp	61	F
Cell Diameter	33	ft
Exhaust velocity (fps)	39.60	fps

uncontrolled

205.50 tpy